



WWYK240146 MONITORING & CONTROL SYSTEMS FOR IWCS



LEGEND
CONTRACTOR
HAUL ROUTE



TINKER AFB, OK
VICINITY MAP

GENERAL NOTES:

- BRAND NAMES: REFERENCE TO SPECIFIC BRAND NAMES OR COMPANIES IS FOR THE PURPOSE OF ESTABLISHING MINIMUM QUALITY STANDARDS. IDENTIFICATION AND GUIDANCE AND IS NOT INTENDED TO LIMIT SELECTION OF OTHER MANUFACTURERS THAT ARE EQUAL OR EXCEED THE SPECIFIED ITEMS IN TERMS OF PHYSICAL PROPERTIES, INCLUDING, COLOR RANGE, FINISH, DURABILITY, APPEARANCE, PERFORMANCE CHARACTERISTICS, AND OTHER FACTORS. OTHER PRODUCTS, MATERIALS, COLORS AND SYSTEMS, MAY BE SUBMITTED FOR EVALUATION AND APPROVAL/DISAPPROVAL BY THE CONTRACTING OFFICER.
- THIS SET OF CONSTRUCTION DOCUMENTS SHALL BE CONSIDERED AS A WHOLE IN THAT THE GENERAL CONTRACTOR AND ALL THE SUB-CONTRACTORS ARE RESPONSIBLE FOR THE INFORMATION PRESENTED ON ALL SHEETS ON THE SET OF DRAWINGS AND ALL SECTIONS OF THE SPECIFICATIONS.
- THE CONTRACTOR IS RESPONSIBLE FOR ERECTING ALL CONSTRUCTION FENCING AND BARRICADES AS REQUIRED TO PROTECT CONSTRUCTION MATERIAL AND TO PREVENT ANY UNAUTHORIZED PERSONNEL FROM ENTERING THE CONSTRUCTION SITE.
- ANY DAMAGE TO THE EXISTING GROUNDS OR FACILITIES CAUSED BY CONSTRUCTION TRAFFIC OR ANY CONSTRUCTION OPERATION SHALL BE REPAIRED OR REPLACED BY THE CONTRACTOR TO MATCH OR EXCEED EXISTING CONDITIONS AT NO ADDITIONAL COST TO THE GOVERNMENT.
- ALL WORK NOTED & LOCATED IN THESE DOCS SHALL BE UNDERSTOOD BY THE CONTRACTOR TO REQUIRE ALL NEW LABOR & MATERIALS UNLESS SPECIFICALLY NOTED TO BE "EXISTING" OR "BY OTHERS".

TIN
UTI
03.

TINKER GATE
PASS & ID
B6611

EAKER
GATE

BASE CIVIL
ENGINEER
B400

CONTRACTING B3

FIRE DEPARTMENT B117

BASE OPERATIONS B240

HRUSKOCY GATE

LANCER GATE

LIBERATOR GATE

HOPE
GATE

PIAZZA GATE

GOTT GATE

TRUCK GATE

PROJECT DRAWING INDEX

SEQ.	SHT.	SHEET TITLE
		GENERAL
1	G-001	GENERAL NOTES & VICINITY MAP
2	G-002	GENERAL SYMBOLS, LEGENDS & ABBREVIATIONS
3	G-101	LIFT STATION LOCATIONS
4	G-102	NETWORK OVERVIEW
		CIVIL
5	C-001	CIVIL GENERAL NOTES AND LEGEND
6	C-100	CIVIL OVERALL SITE PLAN
7	C-101	CIVIL SITE PLAN IW-LS-3
8	C-102	CIVIL SITE PLAN IW-LS-10
9	C-103	CIVIL SITE PLAN IW-LS-2280
10	C-104	CIVIL SITE PLAN IW-LS-6
11	C-501	CIVIL DETAILS
12	C-502	CIVIL CONCRETE VAULT DETAILS
		STRUCTURAL
13	S-001	GENERAL NOTES
		CONTROLS
14	YD101	INSTRUMENTATION DEMO DETAILS IW-LS-3
15	YD102	INSTRUMENTATION DEMO DETAILS IW-LS-10
16	YD103	INSTRUMENTATION DEMO DETAILS IW-LS-2280
17	YD104	INSTRUMENTATION DEMO DETAILS IW-LS-6
18	Y-101	INSTRUMENTATION SITE PLAN IW-LS-3
19	Y-102	INSTRUMENTATION SITE PLAN IW-LS-10
20	Y-103	INSTRUMENTATION SITE PLAN IW-LS-2280
21	Y-104	INSTRUMENTATION SITE PLAN IW-LS-6
22	Y-201	INSTRUMENTATION INTERIOR ROUTING PLAN IW-LS-3
23	Y-202	INSTRUMENTATION INTERIOR ROUTING PLAN IW-LS-10
24	Y-203	INSTRUMENTATION INTERIOR ROUTING PLAN IW-LS-2280
25	Y-204	INSTRUMENTATION INTERIOR ROUTING PLAN IW-LS-6
26	Y-301	INSTRUMENTATION SUMP PUMP DETAIL IW-LS-3
27	Y-302	INSTRUMENTATION SUMP PUMP DETAIL IW-LS-10
28	Y-303	INSTRUMENTATION SUMP PUMP DETAIL IW-LS-2280
29	Y-304N	INSTRUMENTATION NORTH SUMP PUMP DETAIL IW-LS-6
30	Y-304S	INSTRUMENTATION SOUTH SUMP PUMP DETAIL IW-LS-6
		ELECTRICAL
31	E-100	ELECTRICAL OVERALL SITE PLAN

SIGNATURES

CORROSION ENGINEER: (CECE)	DATE:
CE OPERATIONS: (CECO)	DATE:
ZONE MANAGER:	DATE:
CONSTRUCTION MANAGEMENT: (CECE)	DATE:
FIRE DEPARTMENT: (CEFT)	DATE:
SAFETY:	DATE:
INDUSTRIAL HYGIENE:	DATE:
ENVIRONMENTAL:	DATE:
ASBESTOS EVALUATION:	DATE:
COMMUNICATIONS: (COMM)	DATE:
USING AGENCY:	DATE:
REVIEWED BY:	DATE:
REVIEWED BY:	DATE:
DESIGN MANAGER: (CECE)	DATE:
CHIEF DESIGN BRANCH: (CECE)	DATE:
CHIEF ENGINEER DIR: (CECE)	DATE:
BASE CIVIL ENGINEER: (CE)	DATE:

REVISIONS		MANAGEMENT INFORMATION	
MARK	DATE	DESCRIPTION	DATE
		ISSUE DATE: 11/05/2025	
		DESIGN GROUP: HDR	
		DESIGNED BY: JBG	
		DRAWN BY: JBG	
		CHECKED BY: JBG	
		DESIGN FILE LOCATION:	

DRAWING ABBREVIATIONS

A	*****
A LABEL	CLASS A DOOR
A/C	AIR CONDITION
A/C UNIT	AIR CONDITIONING UNIT
A/E	ARCHITECT/ENGINEER
AE	ANCHOR BOLT
ACC	ACCESSIBLE
ACS	AUTOMATIC CONTROL SYSTEM
ACS DR	ACCESS DOOR
ACS PNL	ACCESS PANEL
ACT	ACOUSTIC TILE CEILING
ADA	AMERICANS WITH DISABILITIES ACT
ADMIN	ADMINISTRATION
AFC	ABOVE FINISHED COUNTER
AFF	ABOVE FINISHED FLOOR
AFS	ABOVE FINISHED GRADE
AFS	ABOVE FINISHED SLAB
AGGR	AGGREGATE
AHU	AIR HANDLING UNIT
AIE	AIR INFILTRATION BARRIER
ALT	ALTERNATE
ALUM	ALUMINUM
ANOD	ANODIZE
AP	ACOUSTICAL PANEL CEILING
APPROX	APPROXIMATE
AR	AS REQUIRED
ARCH	ARCHITECT
ASC	ABOVE SUSPENDED CEILING
ASSY	ASSEMBLY
ATC	ACOUSTICAL TILE CEILING
AVG	AVERAGE
AW	ARCHITECTURAL WOODWORK
AWT	ACOUSTICAL WALL TREATMENT

B LABEL	CLASS B DOOR
BALC	BALCONY
BB	BASEBOARD
BC	BOOKCASE
BD	BOARD
BDRY	BOUNDARY
BFF	BELOW FINISH FLOOR
BHMA	BUILDERS HARDWARE
	MANUFACTURER'S ASSOCIATION
BLDG	BUILDING
BLKG	BLOCKING
BLT IN	BUILT-IN
BN	BULLNOSE
BOB	BOTTOM OF STEEL
BOT	BOTTOM
BP	BUILDING PAPER
BRKT	BRACKET
BSMT	BASEMENT
BTWN	BETWEEN
BUR	BUILT-UP ROOFING

C	-----
C CONC	CAST CONCRETE
C LABEL	CLASS C DOOR
CAB	CABINET
CATW	CATWALK
CAV	CAVITY
CBB	CEMENTITIOUS (BACKER) BOARD
CD	CONSTRUCTION DOCUMENTS
CDW	CHILLED DRINKING WATER
CEM PLAS	CEMENT PLASTER
CER	CERAMIC
CF	CONTRACTOR FURNISHED
CF/C	CONTRACTOR
FURNISHED	CONTRACTOR INSTALLED
CFE	CONTRACTOR FURNISHED EQUIPMENT
CLFG	COUNTERFLASHING
CFM	CUBIC FEET PER MINUTE
CFMF	COLD-FORMED METAL FRAMING
CFM2	CUBIC FEET PER SECOND
CG	CORNER GUARD
CI	CAST IRON
CIF	CAST-IN-PLACE
CJ	CONTROL JOINT
CL	CENTER LINE
CLG	CEILING
CLG DIFF	CEILING DIFFUSER
CLG HT	CEILING HEIGHT
LL	COLUMN LINE
CLC	CLOSET
CLR	COLOR
CLRM	CLASSROOM
CMU	CONCRETE MASONRY UNIT
CNDS	CONDENSATE
CDR	CARD READER
CO	CLEANOUT
COL	COLUMN
COMM	COMMUNICATION
CONC	CONCRETE
CONC FLR	CONCRETE FLOOR
CONF	CONFERENCE
CONT	CONTINUE
COORD	COORDINATE
CORR	CORRIDOR
CP	CONCRETE PIPE
CPT	CARPET
CR	CONTROL ROOM
CS	CAST STONE
CSWK	CASEWORK
CT	CERAMIC TILE
CTB	CERAMIC TILE BASE
CTF	CERAMIC TILE FLOOR
CTR	CENTER
CU FT	CUBIC FEET
CW	CASEMENT WINDOW

D	*****
D	DEPTH
D LABEL	CLASS D DOOR
DBL	DOUBLE
DEMO	DEMOLITION
DEPT	DEPARTMENT
DET	DETAIL
DIA	DIAMETER
DIR	DIRECTION
DIST	DISTANCE
DOC	DOCUMENT
DR	DOOR
DS	DOWNSPOUT

```

E *****
E LABEL CLASS E DOOR
EA EACH
EF EACH FACE
EIFS EXTERIOR INSULATION AND FINISH
SYSTEM
EJ EXPANSION JOINT
ES EACH SIDE
EL ELEVATION
ELEV ELEVATOR
ENTR ENTRANCE
EPS EXPANDED POLYSTYRENE BOARD
(INSULATION)
EQ EQUAL
EWC ELECTRIC WATER COOLER
EXP EXPOSED
EXT EXTERIOR
EXT EXTINGUISHER
EXT GREXTERIOR GRADE

```

F	-----
FA	FIRE ALARM
FAAP	FIRE ALARM ANNUNCIATOR PANEL
FAS BD	FASCIA BOARD
FC BRK	FACE BRICK
FCO	FLOOR CLEANOUT
FD	FLOOR DRAIN
FDTN	FOUNDATION
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER CABINET
FED	FEDERAL
FF	FINISH FACE
FF EL	FINISH FLOOR ELEVATION
FI INSUL	FOIL BACKED INSULATION
FGL	FIBERGLASS
FH	FIRE HOSE
FHP	FULL HEIGHT PARTITION
FIN	FINISH
FIN BS	FINISH BOTH SIDES
FIN FLR	FINISH FLOOR
FIN GR	FINISH GRADE
FIXT	FIXTURE
FLDG	FOLDING
FLEX	FLEXIBLE
FLR	FLOORING
FLMT	FLUSH MOUNT
FLR	FLOOR
FM	FACTORY MUTUAL
FOC	FACE OF CONCRETE
FOM	FACE OF MASONRY
FR	FIRE RESISTANT
FRG	FIRE REINFORCED GYPSUM
FRMG	FRAMING
FRP	FIBERGLASS REINFORCED PLASTIC
FRTW	FIRE RETARDANT TREATED WOOD
FS	FEDERAL SPECIFICATION
FSNTR	FASTENER
FT	FEET
FTG	FOOTING
FWC	FACED WALLCOVERING

```

G *****
G NATURAL GAS
GALV GALVANIZED
GB GRAB BAR
GFCI GROUND FAULT CIRCUIT INTERRUPTER
CONTRACTOR INSTALLED
GFGI GROUND FAULT GROUNDING INTERRUPTER
GOVERNMENT INSTALLED
GFRG GLASS-FIBER-REINFORCED GYPSUM BOARD
GLZ GLAZING
GR FL GROUND FLOOR
GUT GUTTER
GYP BD GYPSUM BOARD
GYP PLAS GYPSUM PLASTER

H *****
HB HOSE BIBB
HDPE HIGH DENSITY POLYETHYLENE
HDW HARDWARE
HMD HARDWOOD
HEPA HIGH EFFICIENCY PARTICULATE AIR
(FILTER)
HM HOLLOW METAL
HMD HOLLOW METAL DOOR
HORIZ HORIZONTAL
HT HEIGHT
HYDR HYDRAULIC

```

I	-----
IBC	INTERNATIONAL BUILDING CODE
INSUL	INSULATION
INT	INTERIOR
ILO	IN LIEU OF
J	-----
JAN	JANITOR
K	-----
KPD	KEYPAD
KIT	KITCHEN
KPL	KICKPLATE

L	-----
LAM	LAMINATE
LAV	LAVATORY
LBR	LUMBER
LBS	POUND
LDG	LANDING
LF	LINEAR FEET (FOOT)
LIB	LIBRARY
LIN	LINEAR
LKR	LOCKER
LOC	LOCATION
LT	LIGHT
LVDR	LOUVER DOOR
LVR	LOUVER

M	-----
MACH RM	MACHINE ROOM
MATL	MATERIAL
MAX	MAXIMUM
MC	MOISTURE CONTENT
MD	METAL DECK
MECH	MECHANICAL
MECH RM	MECHANICAL ROOM
MEMB	MEMBRANE
MFR	MILL FINISH
MFG	MANUFACTURER
MID	MIDDLE
MIL STD	MILITARY STANDARD
MIN	MINIMUM, MINUTE
MIRR	MIRROR
MISC	MISCELLANEOUS
MLDG	MOLDING (MOULDING)
MO	MASONRY OPENING
MOD	MODIFY
MB	MOISTURE BARRIER
MTG	MOUNTING
MTL	METAL
MVBL	MOVABLE
MWP	MEMBRANE WATERPROOFING
N	-----
N	NORTH
NA	NOT APPLICABLE
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NIC	NOT IN CONTRACT
NO	NUMBER
NOM	NOMINAL
NP	NO PAINT
NRC	NOISE REDUCTI

C	*****
OA	OVERALL
OC	ON CENTER
OD	OUTSIDE DIAMETER
OFD	OVERFLOW DRAIN
OFF	OFFICE
OG	OBSCURE GLASS
OPH	OPPOSITE HAND
OPNG	OPENING
OPP	OPPOSITE
OPQ	OPAQUE
OWSJ	OPEN WEB STEEL JOIST
OPR	OPERABLE
ORD	OVERFLOW ROOF DRAIN
ORIG	ORIGINAL

P	-----
PA	PUBLIC ADDRESS
PAR	PARAPET
PAT	PATTERN
PB	PULL BOX
PBD	PARTICLEBOARD
PC	PRECAST CONCRETE
PCF	POUNDS PER CUBIC FOOT
PCT	PERCENT
PERF	PERFORATED
PERIM	PERIMETER
PH	PHASE
PI	PILASTER
PL	PROPERTY LINE
PL GL	PLATE GLASS
PLAM	PLASTIC LAMINATE
PLAS	PLASTER
PLBG	PLUMBING
PLG	PLYING
PLYWD	PLYWOOD
PNL	PANEL
PP PL	PUSH/PULL PLATE
PR	PAIR
PRCST	PRECAST
PRKG	PARKING
PS CONC	PRESTRESSED CONCRETE
PSF	POUNDS PER SQUARE FOOT
PSI	POUNDS PER SQUARE INCH
PT	PRESSURE TREATED
PTD	PAPER TOWEL DISPENSER
TRD	THERMOPLASTIC TOWEL DISPENSER
RECEPTACLE	
PTN	PARTITION
PWR	POWER

Q	-----
QT	QUARRY TILE
QTY	QUANTITY


R	RESILIENT BASE
RBM	REINFORCED BRICK MASONRY
RBR	RUBBER
RC	REINFORCED CONCRETE
RPC	REFLECTED CEILING PLAN
RD	ROOF DRAIN
RDG INS	RIGID INSULATION, SO
REC	RECESSED
RCR	RECREATION
REF	REFERENCE
REM	REMOVABLE
REP	REPAIR
REPL	REPLACE
REQ	REQUIRE
REQD	REQUIRED
RESIL	RESILIENT
REST	RESTROOM
RF	RESILIENT FLOORING
RFG	ROOFING
RH	ROOF HATCH
RHR	RIGHT-HAND REVERSE
RL	ROOF LEADER
RLG	RAILING
RM	ROOM
RO	ROUGH OPENING
RSD	ROLLING STEEL DOOR
RV	ROOF VENT
RLV	REVEAL

S *****
SE SPLASH BLOCK
SCHED SCHEDULE
SD SMOKE DETECTOR
SF SQUARE FOOT (FEET)
SFTWSD SFTWOFTWOOD
SGL SINGLE
SHT MTL FLASH SHEET MET
(FLASHING)
SHTHG SHEATHING
SHV SHEAVING
SIM SIMILAR
SJ SCORED JOINT
SKLT SKYLIGHT
SLNT SEALANT
SMK SMOKE
SMLS SEAMLESS
SP EL SPOT ELEVATION
SPEC SPECIFICATION
SQ SQUARE
SQ IN SQUARE INCH
SQ YD SQUARE YARD
SST STAINLESS STEEL
ST STAIRS
STD STANDARD
STL JST STEEL JOIST
STL RF DK STEEL ROOF DECK
STR STORAGE
STR STRINGERS
STRB/HB STROBE/HORN
SUB FL SUBFLOOR
SV SHEET VINYL
SW SIDEWALK

T	-----
T	TREAD
T/S	TUB/SHOWER
TC	TERRA COTTA
TE	TRENCH DRAIN
TEL	TELEPHONE
TEMP	TEMPORARY
TER	TERRAZZO
TF	TOP OF FINISH FLOOR
THK	THICKNESS
TK BC	TACKBOARD
TMPO	TEMPERED GLASS
TN	TRUE NORTH
TOF	TOP OF FOOTING
TOM	TOP OF MASONRY
TOP	TOP OF PARAPET
TOPO	TOPOGRAPHY
TOS	TOP OF SLAB
TRANS	TRANSOM
TRTC	TREATED
TV	TELEVISION

INDEX OF DRAWINGS

NUMBERING SYSTEM:





DISCIPLINE:
C - CIVIL
L - LANDSCAPE
A - ARCHITECTURE
M - MECHANICAL
E - ELECTRICAL
P - PLUMBING
S - STRUCTURAL
K - FOOD SERVICE

DISCIPLINE MODIFIER


SHEET NUMBER WITHIN SERIES

REFER TO A/E/C CAD STANDARD FOR
SHEET NUMBERING STANDARDS


ANNOTATION CALLOUTS/DRAWING SYMBOLS



DRAWING SYMBOLS



DRAWING LEGEND



GENERAL NOTES

1. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH APPLICABLE UNIFIED FACILITY CRITERIA, INTERNATIONAL (IBC) BUILDING CODE REQUIREMENTS, & TINKER AIR FORCE BASE STANDARDS.
2. THE CONTRACTOR SHALL CHECK ALL CONTRACT DOCUMENTS, FIELD CONDITIONS, AND DIMENSIONS FOR ACCURACY AS SHOWN BEFORE PROCEEDING WITH THE CONSTRUCTION. IF THERE ARE ANY QUESTIONS, THE CONTRACTOR SHALL OBTAIN A CLARIFICATION FROM THE ARCHITECT BEFORE PROCEEDING WITH THE WORK IN QUESTION OR RELATED WORK.
3. DRAWINGS SHALL NOT BE SCALED. WRITTEN DIMENSIONS SHALL ALWAYS GOVERN. CONTRACTOR REQUIRING DIMENSIONS NOT NOTED, SHALL CONTACT THE ARCHITECT FOR SUCH INFORMATION PRIOR TO PROCEEDING WITH WORK RELATED TO THOSE DIMENSIONS.
4. LARGE SCALE DRAWINGS TAKE PRECEDENCE OVER SMALL SCALE, DETAILS TAKE PRECEDENCE OVER ALL. CONTRACTOR SHALL NOTIFY ARCHITECT OF CONFLICTS IN WRITING, PRIOR TO PROCEEDING WITH THE WORK IN QUESTION.
5. DETAILS ARE USUALLY KEYED ONLY ONCE (ON THE PLANS OR ELEVATIONS WHEN THEY FIRST OCCUR) AND ARE TYPICAL FOR SIMILAR CONDITIONS THROUGHOUT UNLESS OTHERWISE NOTED.
6. "TYPICAL" OR "TYP." MEANS THAT THE CONDITION IS REPRESENTATIVE FOR ALL SIMILAR CONDITIONS, UNLESS OTHERWISE NOTED. "SIMILAR" OR "SIM." MEANS COMPARABLE CHARACTERISTICS FOR THE CONDITIONS NOTED. VERIFY DIMENSIONS AND ORIENTATION ON PLANS AND ELEVATIONS. "ALIGN" AS USED IN THESE DOCUMENTS MEANS TO ACCURATELY LOCATE FINISHES IN THE SAME PLANE.
7. "AS REQUIRED" MEANS AS REQUIRED BY REGULATORY REQUIREMENTS, BY REFERENCED STANDARDS, BY EXISTING CONDITIONS, BY GENERALLY ACCEPTED CONSTRUCTION PRACTICE OR BY THE CONTRACT DOCUMENTS.
8. ALL DIMENSIONS GIVEN AS CLEAR ARE NOT ADJUSTABLE WITHOUT ARCHITECT/ENGINEER'S APPROVAL.
9. DIMENSIONS ARE TO FACE OF FINISHED WALL UNLESS OTHERWISE NOTED.
10. CONTRACTOR SHALL PROVIDE ALL NECESSARY BLOCKING, BACKING, FRAMING HANGERS OR OTHER SUPPORTS FOR ALL FIXTURES, EQUIPMENT, CABINERY, FURNISHINGS AND ALL OTHER ITEMS REQUIRING SAME.
11. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL CUTTING AND PATCHING REQUIRED FOR PROPER INSTALLATION OF MATERIAL AND EQUIPMENT. PROVIDE DEMOLITION AND PATCH/REPAIR IN ALL AREAS (WHETHER SPECIFICALLY SHOWN OR NOT) TO ACCOMMODATE ALL WORK INCLUDING MECHANICAL, ELECTRICAL, PLUMBING, FIRE PROTECTION.
12. CONTRACTOR SHALL PROTECT, PATCH AND REFINISH TO MATCH EXISTING AREAS TO REMAIN AND AREAS DISTURBED BY NEW CONSTRUCTION, U.O.N.
13. ALL PIPE CONDUIT AND DUCT PENETRATIONS THROUGH FLOORS AND FIRE-RATED WALLS AND CEILINGS SHALL BE SEALED WITH A UL LISTED ASSEMBLY SUCH THAT FIRE RATINGS ARE MAINTAINED.
14. THERE WILL BE ADJACENT AREAS OF THE BUILDING THAT MUST REMAIN OPERATIONAL DURING THE COURSE OF THIS PROJECT. ACCESS TO CEILING AREAS AND SHUT DOWNS OR SERVICES ARE REQUIRED TO BE COORDINATED WITH THE OWNERS REPRESENTATIVE.



AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE
TINKER AFB, OK


WVYK240146
DESIGN & IMPLEMENT MONITORING
CONTROL SYSTEM FOR IWCS, B62516

MANAGEMENT INFORMATION		REVISIONS	
		MARK	DATE DESCRIPTION
ISSUE DATE: 11/05/2025			
DESIGN GROUP: HDR			
DESIGNED BY: BP			
DRAWN BY: SG			
CHECKED BY: KC			
DESIGN FILE LOCATION:			

GENERAL SYMBOLS, LEGENDS & ABBREVIATIONS

SHEET NUMBER

G-002




AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE
TINKER AFB, OK

PROJECT INFORMATION

WWYK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516
TINKER AIR FORCE BASE, OKLAHOMA

MANAGEMENT INFORMATION

ISSUE DATE: 11/05/2025
DESIGN GROUP: HDR
DESIGNED BY: JBG
DRAWN BY: JBG
CHECKED BY: JBG
DESIGN FILE LOCATION:

REVISIONS


MARK	DATE	DESCRIPTION

SHEET TITLE

GENERAL NOTES
AND
VICINITY MAP

SHEET NUMBER

G-101



- KEY NOTES:**
- ① PROVIDE SURGE PROTECTION FOR BACNET COMMUNICATION LINES BETWEEN RTU AND EBI PANEL.
 - ② PROVIDE SURGE PROTECTION FOR BACNET COMMUNICATION LINES BETWEEN W-LS-6N and W-LS-6S.

AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE
TINKER AFB, OK

PROJECT INFORMATION

WWYK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516
TINKER AIR FORCE BASE, OKLAHOMA

REVISIONS	
MARK	DATE DESCRIPTION

MANAGEMENT INFORMATION


ISSUE DATE: 11/05/2025
DESIGN GROUP: HDR
DESIGNED BY: JBG
DRAWN BY: JBG
CHECKED BY: JBG
DESIGN FILE LOCATION:

SHEET TITLE


NETWORK OVERVIEW

SHEET NUMBER

G-102



A1 OVERALL SITE PLAN
C-100 SCALE: 1" = 500'



11/05/2025
RICHARD A. WHITE
28369
OKLAHOMA


WWYK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516

TINKER AIR FORCE BASE, OKLAHOMA

MANAGEMENT INFORMATION		REVISIONS	
ISSUE DATE	DATE	MARK	DESCRIPTION
11/02/2025			
DESIGN GROUP: HDR			
DESIGNED BY: R. WHITE			
DRAWN BY: G. GUERRA			
CHECKED BY: B. WICKERLIN			
DESIGN FILE LOCATION:			


CIVIL OVERALL SITE PLAN

C-100



CAUTION!
EXISTING UNDERGROUND
UTILITIES THIS LOCATION

C-102



GENERAL NOTES

- CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.
- CONTRACTOR AND/OR CONTRACTOR'S INDEPENDENTLY RETAINED EMPLOYEE OR STRUCTURAL DESIGN/GEOTECHNICAL/SAFETY/EQUIPMENT CONSULTANT, IF ANY, SHALL REVIEW THESE PLANS AND AVAILABLE GEOTECHNICAL INFORMATION AND THE ANTICIPATED INSTALLATION SITE(S) WITHIN THE PROJECT WORK AREA IN ORDER TO IMPLEMENT CONTRACTORS TRENCH EXCAVATION SAFETY PROTECTION SYSTEMS, PROGRAMS AND/OR PROCEDURES. THE CONTRACTORS IMPLEMENTATION OF THE SYSTEMS, PROGRAMS AND/OR PROCEDURES SHALL PROVIDE FOR ADEQUATE TRENCH EXCAVATION SAFETY PROTECTION THAT COMPLIES WITH, AS A MINIMUM OSHA STANDARDS FOR TRENCH EXCAVATIONS. CONTRACTOR AND/OR CONTRACTORS INDEPENDENTLY RETAINED EMPLOYEE OR SAFETY CONSULTANT SHALL IMPLEMENT A TRENCH SAFETY PROGRAM IN ACCORDANCE WITH OSHA STANDARDS GOVERNING THE PRESENCE AND ACTIVITIES OF INDIVIDUALS WORKING IN AND AROUND TRENCH EXCAVATION.

KEY NOTES (N)


- FULL DEPTH SAWCUT
- PROPOSED UNDERGROUND COMMUNICATION LINE. SEE INSTRUMENTATION SHEETS FOR ADDITIONAL INFORMATION.
- EXISTING CONCRETE PAVEMENT TO BE REMOVED AND REPLACED. SEE DETAIL C3/C-501.
- FURNISH AND INSTALL SILT FENCE. SEE DETAIL B1/C-501.
- FURNISH AND INSTALL SILT LOG. SEE DETAIL A1/C-501.
- 4" TOP SOIL AND SOD AFTER TRENCH IS BACKFILLED.
- PROPOSED 4'X4' CONCRETE VAULT WITH HS-20 RATED HYDRAULIC ASSIST LID. SEE DETAILS D1/C-502 AND A4/C-502.

LEGEND

- XXXX EXISTING CONTOUR
- EXISTING INSTALLATION PERIMETER FENCE
- X EXISTING FLIGHT LINE SECURITY FENCE
- W W EXISTING WATER LINE
- SS SS EXISTING SANITARY SEWER LINE
- FM FM EXISTING FORCE MAIN
- SD SD EXISTING STORM DRAIN
- G EXISTING GAS LINE
- UGT EXISTING UNDERGROUND TELECOM
- UGE EXISTING UNDERGROUND ELECTRIC
- COMM PROPOSED COMMUNICATION LINE
- FULL DEPTH SAWCUT
- SF SF SILT FENCE
- SILT LOG
- EXISTING CONCRETE PAVEMENT
- EXISTING CONCRETE PAVEMENT TO BE REMOVED AND REPLACED
- EXISTING GRASS AREA
- PROPOSED SOD
- ME ± XX.XX MATCH EXISTING ELEVATION



A1 SITE PLAN IW-LS-6 NORTH AND SOUTH
C-104 SCALE: 1" = 30'



11/05/2025
RICHARD A. WHITE
28369
LICENSED PROFESSIONAL ENGINEER
OKLAHOMA

PROJECT INFORMATION

WWWK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516
TINKER AIR FORCE BASE, OKLAHOMA


REVISIONS	MARK	DATE	DESCRIPTION
ISSUE DATE: 11/5/2025			
DESIGN GROUP: HDR			
DESIGNED BY: R. WHITE			
DRAWN BY: G. GUERRA			
CHECKED BY: B. WICKERLIN			
DESIGN FILE LOCATION:			

SHEET TITLE


CIVIL
SITE PLAN IW-LS-6
NORTH AND SOUTH

SHEET NUMBER

C-104



1



Appr. By:	Rev. BY:	Title: PCC Pavement Repair	
Appr. Date:	Rev. Date:	Rev. No.:	Detail No.: C-1

JOINT SEALER

NEW CONCRETE PAVEMENT

1/2"

3/4"

3"

T

EXISTING CONCRETE

DOWEL IN LUBRICATED SLEEVE

JOINT FILLER

EPOXY IN 18" LONG, 1" DIA. STEEL DOWEL, 9" INTO EACH SECTION @ 12" O.C.


T = THICKNESS

A3

NEW TO EXIST. CONCRETE PAVEMENT JOINT DETAIL

C-501

SCALE: NO SCALE



Appr. By:	Rev. BY:	Title: 8" AC Repair	
Appr. Date:	Rev. Date:	Rev. No.:	Detail No.: A-4


A cross-sectional diagram of a concrete expansion joint. On the left, a concrete slab is shown with a height of 2 inches. Below the concrete is a layer of lime-treated compacted subgrade. An expansion joint is indicated at the base of the concrete slab. To the right of the joint, a 1/2-inch joint filler is shown. Above the filler is a sawcut asphalt layer. Below the filler is an aggregate base layer, which is topped with asphalt pavement. The entire structure is supported by a lime-treated compacted subgrade.

Labels in the diagram include:

- CONCRETE PAVEMENT
- LIME TREATED COMPACTED SUBGRADE
- EXPANSION JOINT
- 1/2" JOINT FILLER
- SAWCUT ASPHALT
- ASPHALT PAVEMENT
- AGGREGATE BASE
- LIME TREATED COMPACTED SUBGRADE

4	5
---	---

MANAGEMENT INFORMATION		REVISIONS	
		MARK	DATE
ISSUE DATE: 11/5/2025			
DESIGN GROUP: HDR			
DESIGNED BY: R. WHITE			
DRAWN BY: G. GUERRA			
CHECKED BY: B. WICKERLIN			
DESIGN FILE LOCATION:			





AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE

TINKER AFB, OK

11/05/2025



RICHARD A. WHITE
28369
OKLAHOMA

WWYK240146

**DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516**

TINKER AIR FORCE BASE, OKLAHOMA

MANAGEMENT INFORMATION		REVISIONS	
ISSUE DATE	DESIGN GROUP	MARK	DESCRIPTION
11/02/2025	HDR		
	DESIGNED BY: R. WHITE		
	DRAWN BY: G. GUERRA		
	CHECKED BY: B. WICKERLIN		
	DESIGN FILE LOCATION:		

SHEET TITLE

**CIVIL
CONCRETE
VAULT DETAILS**

SHEET NUMBER

C-502

1

2

3

4

5

GENERAL STRUCTURAL NOTES (GSN)

GENERAL

G1. SCOPE
THE NOTES ON THIS SHEET AND THE STANDARD STRUCTURAL DETAILS ARE GENERAL AND APPLY TO THE ENTIRE PROJECT WHETHER SPECIFICALLY CALLED OUT OR NOT, EXCEPT WHERE THERE ARE SPECIFIC INDICATIONS TO THE CONTRARY ON STRUCTURAL SHEETS. IF THERE ARE QUESTIONS, THEY SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER AND ANSWERED IN WRITING PRIOR TO CONSTRUCTION.

G2. APPLICABLE SPECIFICATIONS AND CODES
A. UFC 1-200-01 WITH CHANGE 4, DATED 17 DECEMBER 2024
B. UFC 3-301-01 WITH CHANGE 3, DATED 3 FEBRUARY 2025
C. INTERNATIONAL BUILDING CODE, IBC 2024 WITH APPLICABLE EDITIONS OF THE CODE REFERENCED STANDARDS.
D. TINKER AIR FORCE BASE FACILITY STANDARDS
E. ACI 318-19
F. ASCE 7-22

G3. EXISTING DRAWINGS
THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND ELEVATIONS OF EXISTING CONSTRUCTION AS REQUIRED TO COORDINATE NEW CONSTRUCTION. SUBMIT REQUIRED CHANGES FOR APPROVAL. THE PLANS AND DETAILS FOR THE EXISTING STRUCTURES PRESENTED IN THE DRAWINGS ARE FOR REFERENCE ONLY BASED ON THE FOLLOWING AS-BUILT DRAWINGS:
1. "WWYK120068 REPAIR EXHAUST FAN MONITORING SYSTEM, B2122" DATED 07/06/2015.
2. "PROJECT #970244A BUILD ENGINE STAGING BUILDING" DATED 02/03/2000.
3. "AIRCRAFT PROTECTIVE COATING FACILITY: INDUSTRIAL WASTE TREATMENT PLANT" DATED DEC 1975.
4. "P13024 - TINKER AIR FORCE BASE OKLAHOMA CITY, OKLAHOMA CORROSION CONTROL HANGARS, BUILDING 2122" DATED 04/02/2015.
5. "KC-46A TWO-BAY DEPOT MAINTENANCE HANGAR" DATED APRIL 2017.
6. "CENTRAL UTILITIES COMPLEX-VEHICLE ASSEMBLY PLANT" DATED MARCH 13, 2001.

G4. DESIGN CRITERIA
1. APPLIES TO ALL STRUCTURES (UNO)
A. DEAD LOAD:
1. ACTUAL TRIBUTARY STRUCTURE WEIGHT
B. LIVE LOAD:
2. EQUIPMENT PADS 100 PSF
C. WIND:
1. RISK CATEGORY: II
2. ULTIMATE WIND SPEED; V_{ULT}: 109 MPH
3. ALLOWABLE STRESS WIND SPEED; V_{ASD}: 84 MPH
4. EXPOSURE: C
5. DESIGN WIND PRESSURE: 25 PSF
D. SEISMIC:
1. RISK CATEGORY: II
2. IMPORTANCE FACTOR: 1.0
3. SPECTRAL RESPONSE ACCELERATION, S_s = 0.31g
4. SPECTRAL RESPONSE ACCELERATION, S₁ = 0.08g
5. SITE CLASS: D
6. SEISMIC DESIGN CATEGORY: B
7. SPECTRAL RESPONSE COEFFICIENT, S_{DS} = 0.23g
8. SPECTRAL RESPONSE COEFFICIENT, S_{D1} = 0.11g
9. BASIC SEISMIC FORCE RESISTING SYSTEM: SYSTEMS NOT SPECIFICALLY DETAILED FOR SEISMIC RESISTANCE
ASCE CHAPTER 13 - NON-STRUCTURAL COMPONENTS
1.6*S_{DS}*I_p*WEIGHT
11. SEISMIC DESIGN FORCE (MAX): 2.5
12. RESPONSE MODIFICATION FACTOR, R_p = 1.0
13. COMPONENT AMPLIFICATION FACTOR, A_p = 1.0
14. COMPONENT IMPORTANCE FACTOR, I_p = 1.0
10. ANALYSIS PROCEDURE:
E. SNOW LOAD:
1. GROUND SNOW LOAD; P/g: 18 PSF
2. FROST DEPTH: 18 INCHES
F. ICE LOADS:
1. ICE THICKNESS: 1.45 INCHES
2. ICE THICKNESS HEIGHT FACTOR: 1.0
3. DESIGN ICE THICKNESS: 1.5 INCHES
4. DESIGN WEIGHT OF ICE: 7 PSF
G. ROOF RAIN LOAD:
1. 15-MINUTE PRECIPITATION INTENSITY: 7.76 IN/HR
2. 60-MINUTE PRECIPITATION INTENSITY: 3.91 IN/HR
G5. AT THE TIME OF THIS DESIGN, NO GEOTECHNICAL REPORT WAS PREPARED FOR THIS PROJECT. THEREFORE, THE ASSUMED SOIL PRESSURE PER IBC TABLE 1806.2 USED FOR DESIGN IS 1,500 PSF.
G6. SAFETY
SAFETY AND STRUCTURE STABILITY DURING CONSTRUCTION ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR. STRUCTURES HAVE BEEN DESIGNED TO RESIST THE DESIGN LIVE LOADS ONLY AS A COMPLETED STRUCTURE.
G7. OPENINGS
OPENINGS FOR PIPES, DUCTS, CONDUITS, ETC. ARE NOT ALL SHOWN ON THE STRUCTURAL DRAWINGS. COORDINATE AND PROVIDE OPENINGS AS REQUIRED TO ACCOMMODATE ALL WORK SHOWN OR SPECIFIED IN THE CONTRACT DOCUMENTS AND OTHERWISE REQUIRED FOR THE FURNISHING OF A FUNCTIONALLY COMPLETE PROJECT. REINFORCE AROUND OPENINGS PER STANDARD STRUCTURAL DETAILS UNLESS OTHERWISE SHOWN.
G8. SPECIAL INSPECTIONS
THE CONTRACTOR MUST EMPLOY ONE OR MORE APPROVED AGENCIES TO PERFORM INSPECTIONS DURING CONSTRUCTION ON THE TYPES OF WORK LISTED UNDER SECTION 1705 OF THE IBC REQUIRING VERIFICATION AND INSPECTION. THESE INSPECTIONS ARE IN ADDITION TO THE INSPECTIONS DEFINED IN SECTION 110. THE INSPECTING AGENCY MUST PROVIDE REPORTS OF THE SPECIAL INSPECTIONS DIRECTLY TO THE CONTRACTING OFFICER.
G9. STANDARD DETAILS
THE STANDARD DETAILS DEPICT TYPICAL DETAILING TO BE USED ON THIS PROJECT. IF CONDITIONS ARE NOT EXPLICITLY SHOWN ON THE DRAWINGS THEY SHALL BE MADE SIMILAR TO THE STANDARD DETAILS. OBTAIN APPROVAL OF ENGINEER IN WRITING FOR SIMILAR CONDITIONS PRIOR TO CONSTRUCTION.
G10. THE CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND ELEVATIONS OF EXISTING CONSTRUCTION AS REQUIRED TO COORDINATE NEW CONSTRUCTION. SUBMIT REQUIRED CHANGES FOR APPROVAL.
G11. CONTRACTOR TO SUBMIT FOR REVIEW ALL EQUIPMENT SIZES, OPERATING WEIGHTS, VIBRATION FORCES, SUPPORT LOCATIONS, ALONG WITH ANY FLOOR OPENINGS, NOTCHES, AND RECESSES REQUIRED BY SUCH EQUIPMENT. CONCRETE SUPPORT PADS AND/OR FRAMING REQUIRED TO SUPPORT SAID EQUIPMENT SHALL NOT BE FABRICATED AND PLACED UNTIL THE CONCRETE SUPPORT PADS AND/OR FRAMING IS APPROVED TO SUPPORT THE EQUIPMENT.

CONCRETE

C1. DESIGN STRENGTHS:
F_c = 4,500 PSI
F_y = 60,000 PSI
C2. CONCRETE COVER
UNLESS OTHERWISE NOTED, PROVIDE CONCRETE COVER FOR REINFORCING AS FOLLOWS:
CONCRETE DEPOSITED AGAINST EARTH: 3"
CONCRETE IN CONTACT WITH GROUND: 1 1/2"
CONCRETE NOT IN CONTACT WITH GROUND:
SLABS: 3/4"
BEAMS: 1 1/2"
SEE DRAWINGS FOR EXCEPTIONS
C3. SEE SPECIFICATIONS FOR REINFORCING PLACEMENT REQUIREMENTS.
C4. REFER TO OTHER DISCIPLINE DRAWINGS PRIOR TO CONSTRUCTION FOR EMBEDDED ITEMS AND PENETRATIONS NOT SHOWN ON STRUCTURAL DRAWINGS AS REQUIRED TO ACCOMMODATE ALL WORK SHOWN OR SPECIFIED IN THE CONTRACT DOCUMENTS AND OTHERWISE REQUIRED FOR THE FURNISHING OF A FUNCTIONALLY COMPLETE PROJECT. REINFORCE AROUND OPENINGS PER STANDARD STRUCTURAL DETAILS UNLESS OTHERWISE SHOWN.
C5. PROVIDE 3/4" CHAMFERS AT ALL EXPOSED EDGES. NOT ALL CHAMFERS MAY BE SHOWN ON DRAWINGS.
C6. FIELD ADJUST REINFORCING AT OPENINGS AND EMBEDDED ITEMS AS INDICATED.
C7. ANCHOR BOLTS NOT SPECIFIED BY ENGINEER SHALL BE DESIGNED AND CERTIFIED BY A REGISTERED PROFESSIONAL ENGINEER LICENSED IN THE STATE OF OKLAHOMA, RETAINED BY THE CONTRACTOR, IN ACCORDANCE WITH APPLICABLE PROJECT AND CODE REQUIREMENTS. SUBMIT AS A SHOP DRAWING FOR REVIEW AND APPROVAL BY THE ENGINEER. COORDINATE LOCATION, SIZE AND EMBEDMENT PRIOR TO CASTING CONCRETE.
C8. ABSOLUTELY NO WELDING OF REINFORCING BARS OR TORCHING TO BEND REINFORCING BARS SHALL BE ALLOWED.
C9. CONTRACTOR SHALL SUBMIT A CONCRETE PLACEMENT PLAN IDENTIFYING JOINT TYPES, JOINT LOCATIONS AND CONCRETE PLACEMENT SEQUENCE.
C10. ALL CAST IN PLACE AND POST-INSTALLED ANCHORS INDICATED IN THE STRUCTURAL DOCUMENTS SHALL COMPLY WITH CHAPTER 17 OF ACI 318 AND CHAPTER 19 OF THE IBC. ALL EXPANSION AND ADHESIVE ANCHORS SHALL HAVE THE ICC REPORT SHOWING EQUIVALENT LOAD CAPACITY. SUBMIT AND INSTALL PER THE ICC EVALUATION REPORT.
POST INSTALLED ANCHORS
P1. POST-INSTALLED ANCHORS SHALL INCLUDE ADHESIVE ANCHORS (THREADED RODS, BOLTS OR REINFORCING BARS), EXPANSION ANCHORS, AND UNDERCUT ANCHORS INSTALLED INTO HARDENED CONCRETE.
P2. POST-INSTALLED ANCHORS SHALL ONLY BE USED WHERE INDICATED ON THE DRAWINGS. CONTRACTOR SHALL OBTAIN APPROVAL FROM ENGINEER PRIOR TO USING POST-INSTALLED ANCHORS FROM MISSING OR MISPLACED CAST-IN-PLACE ANCHORS.
P3. CARE SHOULD BE TAKEN TO AVOID CONFLICTS WITH EXISTING REINFORCING STEEL AND OTHER EMBEDDED ITEMS WHEN DRILLING HOLES. REINFORCING BARS SHALL NOT BE DAMAGED DURING DRILLING OR ANCHOR INSTALLATION. HOLES SHALL BE DRILLED AND CLEANED PER THE PRODUCT MANUFACTURER'S INSTRUCTIONS. ANCHORS SHALL BE INSTALLED PER THE PRODUCT MANUFACTURER'S INSTRUCTIONS AT NOT LESS THAN MINIMUM EDGE DISTANCES AND/OR SPACING INDICATED IN THE MANUFACTURER'S LITERATURE.
P4. SUBSTITUTION REQUESTS FOR PRODUCTS OTHER THAN THOSE INDICATED ON THE DRAWINGS SHALL BE SUBMITTED TO ENGINEER FOR REVIEW AND APPROVAL. CURRENT PRODUCT ICC-ESR EVALUATION REPORTS SHALL BE INCLUDED WITH THE SUBMITTAL PACKAGE. IF METHODS AND PROCEDURES REQUIRED BY THE BUILDING CODE MAY BE REQUIRED AS PART OF THE SUBMITTAL PACKAGE.
P5. UNLESS NOTES OTHERWISE, THE MINIMUM EMBEDMENT PROVIDED FOR ADHESIVE ANCHORED REINFORCING BARS SHALL DEVELOP THE FULL TENSILE STRENGTH OF THE BARS.
P6. SPECIAL INSPECTION WILL BE PROVIDED FOR ALL POST-INSTALLED ANCHORS AS INDICATED IN SPECIAL INSPECTION REQUIREMENTS PER SPECIFICATION SECTION 05 05 20.

DEFERRED SUBMITTALS:

1. DEFINITION:
DELEGATE DESIGN SUBMITTALS ARE ITEMS FOR WHICH THE FINAL DESIGN OF A SPECIFIC ELEMENT OF THE PERMANENT CONSTRUCTION WORK EXPRESSLY DELEGATED TO A PROPERLY LICENSED AND REGISTERED DESIGN PROFESSIONAL LICENSED IN THE STATE OF OKLAHOMA RETAINED OR EMPLOYED BY THE CONTRACTOR, SUBCONTRACTOR, SUPPLIER OF ANY TIER. "DELEGATED DESIGN" APPLIES ONLY TO PERMANENT WORK THAT WILL BE PART OF THE COMPLETED PROJECT AS A FUNCTIONING WHOLE.
2. DELEGATED DESIGN LIST:
THE FOLLOWING IS A LIST OF DEFERRED SUBMITTALS THAT ARE EXPECTED TO CONTAIN STRUCTURAL CALCULATIONS OF SAFETY-RELATED SYSTEM INFORMATION FOR REVIEW. THESE SUBMITTALS APPLY TO DELEGATED DESIGN SYSTEMS PRIOR TO INSTALLATION OF THE INDICATED STRUCTURAL ELEMENT, EQUIPMENT, DISTRIBUTION SYSTEM, COMPONENT OR ITS ANCHORAGE. THE CONTRACTOR SHALL SUBMIT THE REQUIRED ENGINEER CERTIFICATION, SUPPORTING DATA, AND DRAWINGS FOR REVIEW AND ACCEPTANCE BY THE CONTRACTING OFFICER.

DEFERRED SUBMITTALS

SPEC SECTIONS	ITEM
VARIOUS	ANY EQUIPMENT OR COMPONENT IN WHICH A TECHNICAL SPECIFICATION REQUIRES SUBMITTAL OF EQUIPMENT OR ANCHORAGE SYSTEM CALCULATIONS

MODIFICATIONS TO EXISTING CONCRETE:
EC1. DRILLED HOLE FOR DOWEL SHALL BE THOROUGHLY CLEANED BY WIRE BRUSHING AND AIR PRESSURE OR VACUUM TO REMOVE ALL DRILLING DUST. THE HOLE SHALL THEN BE PARTIALLY FILLED WITH EPOXY AND THE UNCOATED BAR INSERTED, TWISTED AND LEFT IN PLACE.
EC2. AT LOCATIONS WHERE NEW PENETRATIONS FOR CONDUITS ARE REQUIRED, CONTRACTOR SHALL NON-DESTRUCTIVELY LOCATED EXISTING REINFORCING PRIOR TO DRILLING HOLES. LOCATE CONDUITS TO NOT DAMAGE REINFORCING.
EC3. NEW OPENINGS IN EXISTING CONCRETE SHALL BE CUT 1 INCH OVERSIZE, COATED WITH EPOXY BONDING COMPOUND, AND MORTAR FINISHED TO THE REQUIRED FINISH SIZE.
EC4. STRUCTURAL DIMENSIONS RELATED TO OR CONTROLLED BY EXISTING STRUCTURES SHALL BE VERIFIED IN FIELD BY THE CONTRACTOR PRIOR TO CONCRETE WORK.

PROJECT INFORMATION

WWYK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516
TINKER AIR FORCE BASE, OKLAHOMA

11/05/2025

REVISIONS

MARK	DATE	DESCRIPTION

MANAGEMENT INFORMATION


ISSUE DATE: 11/05/2025	DESIGN GROUP: HDR	DESIGNED BY: C. MULDERICK	DRAWN BY: R. NELSON	CHECKED BY: K. TEEMSMA	DESIGN FILE LOCATION:
------------------------	-------------------	---------------------------	---------------------	------------------------	-----------------------

SHEET TITLE

GENERAL NOTES

SHEET NUMBER

S-001



REMOVE EXISTING RTU
PANEL AND LOCATE NEW
PANEL IN THIS LOCATION.



RETAIN WETWELL LEVEL
PRESSURE TRANSDUCER
(PT) ANALOG IN FIELD
WIRING

RETAIN WETWELL LEVEL
PRESSURE TRANSDUCER (PT)
DISCRETE OUT FIELD WIRING

RETAIN FIELD WIRING LISTED
IN TABLE BELOW

NOTES:
1: CONTRACTOR TO CONFIRM FIELD
CONNECTIONS WITH CLIENT
BEFORE REMOVAL OF ANY
EXISTING EQUIPMENT.

FIELD CONNECTION	SIGNAL TYPE	EXISTING SCADAPACK CONNECTION
PUMP 1 START	DO	DO1
PUMP 2 START	DO	DO2
MONACO ALARM	DO	DO3
WETWELL PT	DO	DO4
PUMP 1 ON	DI	DI0
PUMP 2 ON	DI	DI1
PUMP 1 FAULT	DI	DI2
PUMP 2 FAULT	DI	DI3
FAULT RELAY	DI	DI4
WETWELL PT	AI	AI0


01 EXISTING CONDITIONS AND DEMOLITION PLANS IW-LS-3
YD101 SCALE: NTS

02 EXISTING PANEL WIRING AND DEMOLITION PLANS IW-LS-3
YD101 SCALE: NTS



AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE

TINKER AFB, OK



PROJECT INFORMATION

WWWK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516
TINKER AIR FORCE BASE, OKLAHOMA

REVISIONS

MARK	DATE	DESCRIPTION

MANAGEMENT INFORMATION

ISSUE DATE: 11/02/25	DESIGNED BY: S. HORRAS	CHECKED BY: P. KAPADIA
DESIGN GROUP: HDR	DRAWN BY: A. HECK	DESIGN FILE LOCATION:

SHEET TITLE

INSTRUMENTATION
DEMO DETAILS
IW-LS-3

SHEET NUMBER

YD101

1

2

3


4

5

— REMOVE EXISTING RTU PANEL AND LOCATE NEW PANEL IN THIS LOCATION.



01 EXISTING CONDITIONS AND DEMOLITION PLANS IW-LS-2280
YD103 SCALE: NTS



RETAIN FIELD WIRING FOR
PUMPS AND PRESSURE
TRANSMITTERS (PT) LISTED
IN TABLE BELOW


NOTES:

- 1: CONTRACTOR TO CONFIRM FIELD CONNECTIONS WITH CLIENT BEFORE REMOVAL OF ANY EXISTING EQUIPMENT.

FIELD CONNECTION	SIGNAL TYPE	EXISTING SCADAPACK CONNECTION
PUMP 1 START	DO	DO1
PUMP 2 START	DO	DO2
MONACO ALARM	DO	DO3
WETWELL PT	DO	DO4
PUMP 1 ON	DI	DI0
PUMP 2 ON	DI	DI1

02 EXISTING PANEL WIRING AND DEMOLITION PLANS IW-LS-2280
YD103 SCALE: NTS

Air Force Materiel Command
72 ABW Civil Engineer Directorate
Tinker AFB, OK



WWWK240146
DESIGN & IMPLEMENT MONITORING
CONTROL SYSTEM FOR IWCS, B62516
TINKER AIR FORCE BASE, OKLAHOMA

MANAGEMENT INFORMATION		REVISIONS		DATE	DESCRIPTION
		MARK			
ISSUE DATE: 11/5/2025					
DESIGN GROUP: HDR					
DESIGNED BY: S. HORRAS					
DRAWN BY: A. HECK					
CHECKED BY: P. KAPADIA					
DESIGN FILE LOCATION:					

**INSTRUMENTATION
DEMO DETAILS
IW-LS-2280**


SHEET NUMBER-

YD103



01
YD104

EXISTING CONDITIONS AND DEMOLITION PLANS IW-LS-6N & IW-LS-6S
SCALE: NTS



RETAIN FIELD WIRING FOR
PUMPS AND PRESSURE
TRANSMITTERS (PT) LISTED
IN TABLE BELOW FOR WET
WELL NORTH (WWN) AND
WET WELL SOUTH (WWS)

NOTES:




- 1: CONTRACTOR TO CONFIRM FIELD CONNECTIONS WITH CLIENT BEFORE REMOVAL OF ANY EXISTING EQUIPMENT.

FIELD CONNECTION	SIGNAL TYPE	EXISTING SCADAPACK CONNECTION
WWN PUMP 1 START	DO	DO11
WWN PUMP 2 START	DO	DO10
WWS PUMP 1 START	DO	DO9
WWS PUMP 2 START	DO	DO8
WETWELL NORTH PT	DO	DO2
WETWELL SOUTH PT	DO	DO3
WWN PUMP 1 ON	DI	DI0
WWN PUMP 2 ON	DI	DI1
WWS PUMP 1 ON	DI	DI2
WWS PUMP 2 ON	DI	DI3
WETWELL NORTH PT	AI	AI0
WETWELL SOUTH PT	AI	AI1

02
YD104

EXISTING PANEL WIRING AND DEMOLITION PLANS IW-LS-6N & IW-LS-6S
SCALE: NTS

REVISIONS		MANAGEMENT INFORMATION	
MARK	DATE	DESCRIPTION	DESIGNER
			ISSUE DATE: 11/02/25
			DESIGN GROUP: HDR
			DESIGNED BY: S. HORRAS
			DRAWN BY: A. HECK
			CHECKED BY: P. KAPADIA
			DESIGN FILE LOCATION:




1. CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
2. CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.
3. ALL PENETRATIONS ARE TO BE SEALED WITH APPROPRIATE SEALANT OR FIRESTOPPING SPECIFIC TO ASSEMBLY BEING PENETRATED. ALL PENETRATIONS TO BE SEALED, TYPICAL.

- ① SEE CIVIL PLANS SHEET: WWYK240146 C-101 FOR ADDITIONAL INFORMATION AND FOR CONTINUATION OF LINE OUT OF BUILDING 214.
- ② SEE STRUCTURAL PLANS SHEET: WWYK240146 S-001 NOTES: G10, AND EC1-EC4, FOR ADDITIONAL INFORMATION FOR WALL PENETRATION.
- ③ HONEYWELL PANEL LOCATED ON THE SECOND FLOOR OF BUILDING 214. SEE SHEET Y-201 FOR DETAILED LOCATION OF THE HONEYWELL PANEL.
- ④ CONDUIT TO RUN ALONG EXTERIOR OF BUILDING NEXT TO EXISTING CONDUIT.


COMM	PROPOSED COMM LINE
------	--------------------

</	
---	--





01 SITE PLAN IW-LS-2280
Y-103 SCALE: 1"=20'



GENERAL NOTES:

- 1. CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
- 2. CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.
- 3. ALL PENETRATIONS ARE TO BE SEALED WITH APPROPRIATE SEALANT OR FIRESTOPPING SPECIFIC TO ASSEMBLY BEING PENETRATED. ALL PENETRATIONS TO BE SEALED, TYPICAL.

KEY NOTES:


- 1 SEE CIVIL PLANS SHEET: WWYK240146 C-103 FOR ADDITIONAL INFORMATION AND FOR CONTINUATION OF LINE OUT OF BUILDING 2280.
- 2 SEE STRUCTURAL PLANS SHEET: WWYK240146 S-001 NOTES: G10, AND EC1-EC4, FOR ADDITIONAL INFORMATION FOR WALL PENETRATION.
- 3 HONEYWELL PANEL LOCATED ON THE SECOND FLOOR OF BUILDING 2280. SEE SHEET Y-203 FOR DETAILED LOCATION OF THE HONEYWELL PANEL.
- 4 CONDUIT TO RUN ALONG EXTERIOR OF BUILDING NEXT TO EXISTING CONDUIT.

LEGEND:

COMM PROPOSED COMM LINE



AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE
TINKER AFB, OK



WWYK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516

TINKER AIR FORCE BASE, OKLAHOMA


MANAGEMENT INFORMATION		REVISIONS	
ISSUE DATE	11/02/25	MARK	DATE
DESIGN GROUP	HDR		
DESIGNED BY	S. HORRAS		
DRAWN BY	A. HECK		
CHECKED BY	P. KAPADIA		
DESIGN FILE LOCATION:			

SHEET TITLE

INSTRUMENTATION
SITE PLAN
IW-LS-2280


SHEET NUMBER

Y-103



01
Y-201

BUILDING 214 SECOND FLOOR INTERIOR ROUTING PLAN IW-LS-3
SCALE: NTS



GENERAL NOTES:

- CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.
- WALL THICKNESS TO BE FIELD VERIFIED BY CONTRACTOR.

KEY NOTES:


- SEE CIVIL PLANS SHEET: WWYK240146 C-101 FOR ADDITIONAL INFORMATION AND FOR CONTINUATION OF LINE OUT OF BUILDING 214.
- SEE STRUCTURAL PLANS SHEET: WWYK240146 S-001 FOR ADDITIONAL INFORMATION FOR WALL PENETRATION.
- CONDUIT TO RUN ALONG EXTERIOR OF BUILDING NEXT TO EXISTING CONDUIT.

LEGEND:

COMM PROPOSED COMM LINE



AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE
TINKER AFB, OK



WWYK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516

TINKER AIR FORCE BASE, OKLAHOMA


MANAGEMENT INFORMATION		REVISIONS		PROJECT INFORMATION	
ISSUE DATE	DESIGN GROUP	MARK	DATE	DESCRIPTION	
11/02/25	HDR				
	DESIGNED BY: S. HORRAS				
	DRAWN BY: A. HECK				
	CHECKED BY: P. KAPADIA				
	DESIGN FILE LOCATION:				

SHEET TITLE

INSTRUMENTATION
INTERIOR ROUTING PLAN
IW-LS-3

SHEET NUMBER

Y-201



①②

EXISTING PANEL
B3706_CP01


B3706

1. CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
2. CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.
3. WALL THICKNESS TO BE FIELD VERIFIED BY CONTRACTOR.

- ① SEE CIVIL PLANS SHEET: WWYK240146 C-102 FOR ADDITIONAL INFORMATION AND FOR CONTINUATION OF LINE OUT OF BUILDING 3706.
- ② SEE STRUCTURAL PLANS SHEET: WWYK240146 S-001 FOR ADDITIONAL INFORMATION FOR WALL PENETRATION.
- ③ CONDUIT TO RUN ALONG INTERIOR OF BUILDING NEXT TO EXISTING CONDUIT.

COMM	PROPOSED COMM LINE
------	--------------------

SHEET TITLE INSTRUMENTATION INTERIOR ROUTING PLAN IW-LS-10	SHEET NUMBER Y-202
--	--



01 BUILDING 2280 SECOND FLOOR INTERIOR ROUTING PLAN IW-LS-10
Y-203 SCALE: NTS

GENERAL NOTES:

1. CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
2. CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.
3. ALL PENETRATIONS ARE TO BE SEALED WITH APPROPRIATE SEALANT OR FIRESTOPPING SPECIFIC TO ASSEMBLY BEING PENETRATED. ALL PENETRATIONS TO BE SEALED, TYPICAL.
4. WALL THICKNESS TO BE FIELD VERIFIED BY CONTRACTOR.

KEY NOTES:


- ① SEE CIVIL PLANS SHEET: WWYK240146 C-103 FOR ADDITIONAL INFORMATION AND FOR CONTINUATION OF LINE OUT OF BUILDING 2280.
- ② SEE STRUCTURAL PLANS SHEET: WWYK240146 S-001 NOTES: G10, AND EC1-EC4, FOR ADDITIONAL INFORMATION FOR WALL PENETRATION.
- ③ CONDUIT TO RUN ALONG EXTERIOR OF BUILDING NEXT TO EXISTING CONDUIT.

LEGEND:

COMM PROPOSED COMM LINE



AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE
TINKER AFB, OK




WWYK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516
TINKER AIR FORCE BASE, OKLAHOMA

MANAGEMENT INFORMATION		REVISIONS	
MARK	DATE	DESCRIPTION	DATE
ISSUE DATE: 11/5/2025			
DESIGN GROUP: HDR			
DESIGNED BY: S. HORRAS			
DRAWN BY: A. HECK			
CHECKED BY: P. KAPADIA			
DESIGN FILE LOCATION:			

SHEET TITLE
INSTRUMENTATION
INTERIOR ROUTING PLAN
IW-LS-2280

SHEET NUMBER
Y-203





BUILDING 2136 SECOND FLOOR INTERIOR ROUTING PLAN IW-LS-6N & IW-LS-6S
SCALE: NTS

1. CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
2. CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.
3. ALL PENETRATIONS ARE TO BE SEALED WITH APPROPRIATE SEALANT OR FIRESTOPPING SPECIFIC TO ASSEMBLY BEING PENETRATED. ALL PENETRATIONS TO BE SEALED, TYPICAL.
4. WALL THICKNESS TO BE FIELD VERIFIED BY CONTRACTOR.

- ① SEE CIVIL PLANS SHEET: WWYK240146 C-104 FOR ADDITIONAL INFORMATION AND FOR CONTINUATION OF LINE OUT OF BUILDING 2136.
- ② SEE STRUCTURAL PLANS SHEET: WWYK240146 S-001
NOTES: G10, AND EC1-EC4, FOR ADDITIONAL INFORMATION FOR WALL PENETRATION.

COMM	
	PROPOSED COMM LINE

 AIR FORCE MATERIEL COMMAND 72 ABW CIVIL ENGINEER DIRECTORATE TINKER AFB, OK			
PROJECT INFORMATION		WWWK240146 DESIGN & IMPLEMENT MONITORING & CONTROL SYSTEM FOR IWCS, B62516	
REVISIONS		TINKER AIR FORCE BASE, OKLAHOMA	
MANAGEMENT INFORMATION			
ISSUE DATE: 11/5/2025	MARK	DATE	DESCRIPTION
DESIGN GROUP: HDR			
DESIGNED BY: S. HORRAS			
DRAWN BY: A. HECK			
CHECKED BY: P. KAPADIA			
DESIGN FILE LOCATION:			
INSTRUMENTATION INTERIOR ROUTING PLAN IW-LS-6			
Y-204			



GENERAL NOTES:

- CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.

KEY NOTES:

- PLACE KEYED HOA SWITCHES ON FRONT OF RTU ENCLOSURE. COORDINATE WITH ITWP PERSONNEL FOR MANUFACTURER AND KEY CODE. PROVIDE CONTACT BLOCK TO MONITOR AUTO POSITION.
- PLACE CONTROL RELAY AND CT SWITCH IN PUMP START PANEL.
- DESIGN PANEL TO BRING ALL AVAILABLE RTU I/O TO FIELD TERMINAL STRIPS. ALL FIELD DEVICES TO CONNECT TO PANEL THROUGH FIELD TERMINAL STRIPS.
- EXISTING HYDROSTATIC (PRESSURE) LEVEL SENSOR.
- PROVIDE AND INSTALL ONICON F-4300 CLAMP ON FLOW METER AND TRANSMITTER. SEE SPECIFICATIONS SECTION 2.4 FOR FLOW METER SELECTION.
- PROVIDE FAN AND VENT FOR AIR FLOW. PROVIDE THERMOSTAT FOR FAN CONTROL. PROVIDE SHROUDS FOR NEMA 3R.
- PROVIDE PANEL 120VAC PANEL HEATER WITH INTEGRAL T-STAT.
- PROVIDE SENSOR TO MONITOR PANEL INTERNAL TEMPERATURE.
- PROVIDE DOOR SWITCH TO MONITOR DOOR OPEN.
- PROVIDE SURGE PROTECTION FOR BACNET COMMUNICATION LINES BETWEEN RTU AND EBI PANEL.
- PLACE HORN SILENCE SWITCH ON FRONT OF RTU PANEL.

LEGEND:

- — — — — PROPOSED PANEL WIRING
- - - - - PROPOSED FIELD WIRING

AFMCS
AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE
TINKER AFB, OK

STEPHEN HORRAS
35430
11/05/25

PROJECT INFORMATION

WWYK240146

DESIGN & IMPLEMENT MONITORING & CONTROL SYSTEM FOR IWCS, B62516

TINKER AIR FORCE BASE, OKLAHOMA

REVISIONS	MARK	DATE	DESCRIPTION
1			
2			
3			
4			
5			

MANAGEMENT INFORMATION


ISSUE DATE: 11/02/25
DESIGN GROUP: HDR
DESIGNED BY: S. HORRAS
DRAWN BY: A. HECK
CHECKED BY: P. KAPADIA
DESIGN FILE LOCATION:

SHEET TITLE

INSTRUMENTATION
LIFT STATION DETAIL
IW-LS-10

SHEET NUMBER

Y-302



GENERAL NOTES:

- CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.

KEY NOTES:

- PLACE KEYED HOA SWITCHES ON FRONT OF RTU ENCLOSURE. COORDINATE WITH ITWP PERSONNEL FOR MANUFACTURER AND KEY CODE. PROVIDE CONTACT BLOCK TO MONITOR AUTO POSITION.
- PLACE CONTROL RELAY AND CT SWITCH IN PUMP START PANEL.
- DESIGN PANEL TO BRING ALL AVAILABLE RTU I/O TO FIELD TERMINAL STRIPS. ALL FIELD DEVICES TO CONNECT TO PANEL THROUGH FIELD TERMINAL STRIPS.
- EXISTING HYDROSTATIC (PRESSURE) LEVEL SENSOR.
- PROVIDE AND INSTALL ONICON F-4300 CLAMP ON FLOW METER AND TRANSMITTER. SEE SPECIFICATIONS SECTION 2.4 FOR FLOW METER SELECTION.
- PROVIDE FAN AND VENT FOR AIR FLOW. PROVIDE THERMOSTAT FOR FAN CONTROL. PROVIDE SHROUDS FOR NEMA 3R.
- PROVIDE PANEL 120VAC PANEL HEATER WITH INTEGRAL T-STAT.
- PROVIDE SENSOR TO MONITOR PANEL INTERNAL TEMPERATURE.
- PROVIDE DOOR SWITCH TO MONITOR DOOR OPEN.
- PROVIDE SURGE PROTECTION FOR BACNET COMMUNICATION LINES BETWEEN RTU AND EBI PANEL.
- PLACE HORN SILENCE SWITCH ON FRONT OF RTU PANEL.
- PROVIDE AND INSTALL SUMP PUMP RATED AT MINIMUM 2.1 GPM AND 15 FEET OF HEAD TO KEEP STORM WATER FROM FILLING PIT AND DISCHARGE INTO EXISTING INTERIOR METAL CONTAINMENT BASIN. PROVIDE A 120 VAC GFCI CIRCUIT IN RTU PANEL FOR SUMP PUMP POWER.
- PROVIDE PIPE SUPPORT FOR NEW SUMP PUMP BASED ON SITE SPECIFIC NEEDS. INSTALL TO MINIMIZE INTERFERENCE WITH OPERATION OF WET WELL.
- PROVIDE HEAT TRACING TO NEW SUMP AND ASSOCIATED PIPING.
- PROVIDE A SUMP PUMP WITH AN INTEGRAL FLOAT SWITCH, TO EMPTY OUT WATER IN THE OUTER TANK TO THE INNER TANK WHICH HOLDS THE IWW. THE SUMP PUMP TO BE SUPPLIED WITH A MOTOR STARTER.

LEGEND:

— PROPOSED PANEL WIRING

- - - PROPOSED FIELD WIRING

PROJECT INFORMATION

WWYK240146

DESIGN & IMPLEMENT MONITORING & CONTROL SYSTEM FOR IWCS, B62516

TINKER AIR FORCE BASE, OKLAHOMA


REVISIONS	MARK	DATE	DESCRIPTION
1			
2			
3			
4			
5			

MANAGEMENT INFORMATION

ISSUE DATE: 11/6/2025
DESIGN GROUP: HDR
DESIGNED BY: S. HORRAS
DRAWN BY: A. HECK
CHECKED BY: P. KAPADIA
DESIGN FILE LOCATION:

INSTRUMENTATION LIFT STATION DETAIL IW-LS-2280

SHEET NUMBER: **Y-303**



GENERAL NOTES:

- CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
- CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.

KEY NOTES:

- PLACE KEYED HOA SWITCHES ON FRONT OF RTU ENCLOSURE. COORDINATE WITH ITWP PERSONNEL FOR MANUFACTURER AND KEY CODE. PROVIDE CONTACT BLOCK TO MONITOR AUTO POSITION.
- PLACE CONTROL RELAY AND CT SWITCH IN PUMP START PANEL.
- DESIGN PANEL TO BRING ALL AVAILABLE RTU I/O TO FIELD TERMINAL STRIPS. ALL FIELD DEVICES TO CONNECT TO PANEL THROUGH FIELD TERMINAL STRIPS.
- EXISTING HYDROSTATIC (PRESSURE) LEVEL SENSOR.
- PROVIDE AND INSTALL ONICON F-4300 CLAMP ON FLOW METER AND TRANSMITTER. SEE SPECIFICATIONS SECTION 2.4 FOR FLOW METER SELECTION.
- PROVIDE FAN AND VENT FOR AIR FLOW. PROVIDE THERMOSTAT FOR FAN CONTROL. PROVIDE SHROUDS FOR NEMA 3R.
- PROVIDE PANEL 120VAC PANEL HEATER WITH INTEGRAL T-STAT.
- PROVIDE SENSOR TO MONITOR PANEL INTERNAL TEMPERATURE.
- PROVIDE DOOR SWITCH TO MONITOR DOOR OPEN.
- PROVIDE SURGE PROTECTION FOR BACNET COMMUNICATION LINES BETWEEN RTU AND EBI PANEL.
- PLACE HORN SILENCE SWITCH ON FRONT OF RTU PANEL.

LEGEND:

— PROPOSED PANEL WIRING

- - - PROPOSED FIELD WIRING

PROJECT INFORMATION

WWYK240146

DESIGN & IMPLEMENT MONITORING & CONTROL SYSTEM FOR IWCS, B62516

TINKER AIR FORCE BASE, OKLAHOMA

REVISIONS	MARK	DATE	DESCRIPTION
1			
2			
3			
4			
5			

MANAGEMENT INFORMATION


ISSUE DATE: 1/16/2025	DESIGN GROUP: HDR	DESIGNED BY: S. HORRAS	DRAWN BY: A. HECK	CHECKED BY: P. KAPADIA	DESIGN FILE LOCATION:
-----------------------	-------------------	------------------------	-------------------	------------------------	-----------------------

SHEET TITLE

INSTRUMENTATION NORTH LIFT STATION DETAIL IW-LS-6N

SHEET NUMBER

Y-304N



- GENERAL NOTES:**
- CONTRACTOR TO VERIFY LOCATIONS OF EXISTING UTILITIES AND ALL SURVEY INFORMATION PRIOR TO CONSTRUCTION.
 - CONTRACTOR SHALL ADJUST MANHOLES AND VALVE BOXES WITHIN PROJECT LIMIT TO FINISH GRADE.
- KEY NOTES:**
- PLACE KEYED HOA SWITCHES ON FRONT OF RTU ENCLOSURE. COORDINATE WITH ITWP PERSONNEL FOR MANUFACTURER AND KEY CODE. PROVIDE CONTACT BLOCK TO MONITOR AUTO POSITION.
 - PLACE CONTROL RELAY AND CT SWITCH IN PUMP START PANEL.
 - DESIGN PANEL TO BRING ALL AVAILABLE RTU I/O TO FIELD TERMINAL STRIPS. ALL FIELD DEVICES TO CONNECT TO PANEL THROUGH FIELD TERMINAL STRIPS.
 - EXISTING HYDROSTATIC (PRESSURE) LEVEL SENSOR.
 - PROVIDE AND INSTALL ONICON F-4300 CLAMP ON FLOW METER AND TRANSMITTER. SEE SPECIFICATIONS SECTION 2.4 FOR FLOW METER SELECTION.
 - PROVIDE FAN AND VENT FOR AIR FLOW. PROVIDE THERMOSTAT FOR FAN CONTROL. PROVIDE SHROUDS FOR NEMA 3R.
 - PROVIDE PANEL 120VAC PANEL HEATER WITH INTEGRAL T-STAT.
 - PROVIDE SENSOR TO MONITOR PANEL INTERNAL TEMPERATURE.
 - PROVIDE DOOR SWITCH TO MONITOR DOOR OPEN.
 - PROVIDE SURGE PROTECTION FOR BACNET COMMUNICATION LINES BETWEEN RTU AND EBI PANEL.
 - PLACE HORN SILENCE SWITCH ON FRONT OF RTU PANEL.

LEGEND:

— — — — — PROPOSED PANEL WIRING
- - - - - PROPOSED FIELD WIRING

AFMC
AIR FORCE MATERIEL COMMAND
72 ABW CIVIL ENGINEER DIRECTORATE
TINKER AFB, OK

STEPHEN HORRAS
35430
Oklahoma
11/05/25

PROJECT INFORMATION

WWYK240146
DESIGN & IMPLEMENT MONITORING
& CONTROL SYSTEM FOR IWCS, B62516
TINKER AIR FORCE BASE, OKLAHOMA


REVISIONS	MARK	DATE	DESCRIPTION
1			
2			
3			
4			
5			

MANAGEMENT INFORMATION

ISSUE DATE: 11/02/25
DESIGN GROUP: HDR
DESIGNED BY: S. HORRAS
DRAWN BY: A. HECK
CHECKED BY: P. KAPADIA
DESIGN FILE LOCATION:

INSTRUMENTATION
SOUTH LIFT STATION
DETAIL
IW-LS-6S

Y-304S



0 500' 1000