

ENERGY CODE COMMISSIONING NOTES

SECTION 408.2.5 DOCUMENTATION REQUIREMENTS

IT SHALL BE THE COMMISSIONING AGENT'S RESPONSIBILITY TO PROVIDE ALL BELOW NOTED DOCUMENTS WITHIN 90 DAYS OF CERTIFICATE OF OCCUPANCY:

- A. AS-BUILT DRAWINGS - DRAWINGS SHALL INCLUDE THE LOCATION AND PERFORMANCE DATA OF ALL PIECES OF MECHANICAL EQUIPMENT.
 - A.1. AS BUILT DRAWINGS TO BE FURNISHED TO THE COMMISSIONING AGENT BY THE MECHANICAL CONTRACTOR.
- B. OPERATING AND MAINTENANCE MANUALS - MANUALS SHALL INCLUDE THE FOLLOWING:
 1. SUBMITTAL DATA ON ALL PIECES OF EQUIPMENT REQUIRING MAINTENANCE.
 2. MANUFACTURER'S OPERATIONS AND MAINTENANCE DATA ON ALL PIECES OF EQUIPMENT. ROUTINE MAINTENANCE ACTIONS SHALL BE CLEARLY IDENTIFIED.
 3. NAME AND ADDRESS AND PHONE NUMBER OF AT LEAST ONE (1) SERVICE PROVIDER.
 4. MECHANICAL CONTROL SYSTEMS MAINTENANCE AND CALIBRATION INFORMATION INCLUDING WIRING DIAGRAMS, EQUIPMENT AND SYSTEM SCHEMATICS, AND CONTROL SEQUENCES OF OPERATIONS. DESIRED OR FIELD DETERMINED SETPOINTS SHALL BE PERMANENTLY RECORDED ON CONTROL DRAWINGS AT ALL CONTROL DEVICES, OR FOR DIGITAL CONTROL SYSTEMS, IN THE SYSTEM PROGRAMMING INSTRUCTIONS.
 5. A NARRATIVE ON HOW EACH MECHANICAL SYSTEM IS INTENDED TO OPERATE, INCLUDING RECOMMENDED SETPOINTS.
- C. SYSTEM BALANCE REPORT - REPORT SHALL BE IN COMPLIANCE WITH IECC 408.2.2 AND INCLUDE THE FOLLOWING:
 1. ALL AIR SYSTEMS BALANCED. THIS SHALL INCLUDE ALL AIR OUTLETS. SYSTEMS SHALL BE BALANCED IN ACCORDANCE WITH IMC CHAPTER 6 AND IECC SECTION 408.2.2
 2. ALL HYDRONIC SYSTEMS BALANCED. THIS SHALL INCLUDE ALL HYDRONIC BALANCING VALVES. EACH SYSTEM SHALL BE PROPERLY BALANCED TO MINIMIZE THROTTLING LOSSES, AND THEN THE PUMP IMPELLER SHALL BE TRIMMED OR PUMP SPEED SHALL BE ADJUSTED TO MEET DESIGN FLOW CONDITIONS. HYDRONIC SYSTEMS SHALL BE BALANCED IN ACCORDANCE WITH IMC CHAPTER 6 AND IECC SECTION 408.2.2.
- D. FINAL COMMISSIONING REPORT - A REPORT OF TEST PROCEDURES AND RESULTS IDENTIFIED AS THE "FINAL COMMISSIONING REPORT" SHALL BE DELIVERED TO THE BUILDING OWNER. THE REPORT SHALL INCLUDE THE FOLLOWING:
 1. LIST OF FUNCTIONAL TESTS USED DURING THE COMMISSIONING PROCESS ON EACH PIECE OF EQUIPMENT.
 2. RESULTS OF ALL FUNCTIONAL TESTS ON ALL PIECES OF EQUIPMENT.
 3. LIST OF DEFICIENCIES FOUND AND CORRESPONDING CORRECTIVE MEASURES EITHER IMPLEMENTED OR PROPOSED ON EACH PIECE OF EQUIPMENT.
 4. LIST OF EQUIPMENT NOT ABLE TO BE FUNCTIONALLY TESTED DUE TO CURRENT CLIMATE CONDITIONS. THESE PIECES OF EQUIPMENT WILL FUNCTIONALLY TESTED ONCE CLIMATE CHANGES ALLOW.

SECTION 408.2.1 COMMISSIONING REQUIREMENTS

PRIOR TO PASSING THE FINAL MECHANICAL INSPECTION, THE REGISTERED DESIGN PROFESSIONAL (OR OTHERWISE APPROVED INDIVIDUAL) SHALL PROVIDE EVIDENCE OF THE MECHANICAL SYSTEMS COMMISSIONING AND COMPLETION IN ACCORDANCE WITH THE BELOW NOTED REQUIREMENTS:

- A. COMMISSIONING PLAN - A COMMISSIONING PLAN SHALL BE DEVELOPED BY A REGISTERED DESIGN PROFESSIONAL (OR OTHERWISE APPROVED INDIVIDUAL) AND SHALL INCLUDE THE FOLLOWING:
 1. A NARRATIVE OF THE ACTIVITIES THAT WILL BE ACCOMPLISHED DURING EACH PHASE OF THE COMMISSIONING PROCESS INCLUDING THE NECESSARY INTENDED TO ACCOMPLISH EACH OF THE ACTIVITIES IN THE COMMISSIONING PROCESS DURING EACH PHASE.
 2. A LISTING OF THE MECHANICAL EQUIPMENT, APPLIANCE, OR SYSTEMS INTENDED TO BE COMMISSIONED ALONG WITH AN EQUIPMENT SPECIFIC NARRATIVE ON THE TESTS FOR EACH SPECIFIC MECHANICAL EQUIPMENT, APPLIANCE, OR SYSTEM.
 3. A LISTING OF THE FUNCTIONS TO BE TESTED ON EACH MECHANICAL EQUIPMENT, APPLIANCE, OR SYSTEM. FUNCTIONAL TESTING SHALL INCLUDE COMPLETE CALIBRATION ON ALL COMPONENTS, CONFIRMATION OF ALL APPLICABLE MODES OF OPERATION INCLUDING BUT NOT LIMITED TO HEATING, COOLING, VENTILATION, AND ECONOMIZER.
 4. CONDITIONS UNDER WHICH THE ABOVE NOTED TESTS ARE TO BE PERFORMED. IF CLIMATE CONDITIONS PROHIBIT THE FUNCTIONAL TESTING OF CERTAIN MODES OF OPERATIONS, THEN THOSE SPECIFIC TESTS MAY BE POSTPONED UNTIL SUCH CLIMATE CONDITIONS ALLOW FOR CORRESPONDING TESTS.
 5. MEASURABLE PASS/FAIL CRITERIA FOR ALL FUNCTIONAL TESTS.
- B. SYSTEM ADJUSTING AND BALANCING - THE ENTIRE MECHANICAL SYSTEM SHALL BE BALANCED IN ACCORDANCE WITH PROJECT SPECIFICATIONS AND THE FOLLOWING:
 1. ALL AIR SYSTEMS BALANCED. THIS SHALL INCLUDE ALL AIR OUTLETS AND ZONE TERMINAL DEVICE. SYSTEMS SHALL BE BALANCED IN ACCORDANCE WITH IMC CHAPTER 6 AND IECC SECTION 408.2.2.1.
 2. ALL HYDRONIC SYSTEMS BALANCED. THIS SHALL INCLUDE ALL HYDRONIC BALANCING VALVES. EACH SYSTEM SHALL BE PROPERLY BALANCED TO MINIMIZE THROTTLING LOSSES, AND THEN THE PUMP IMPELLER SHALL BE TRIMMED OR PUMP SPEED SHALL BE ADJUSTED TO MEET DESIGN FLOW CONDITIONS. HYDRONIC SYSTEMS SHALL BE BALANCED IN ACCORDANCE WITH IMC CHAPTER 6 AND IECC SECTION 408.2.2.
 3. ALL CONTROLS SHALL BE CALIBRATED AND ADJUSTED TO ENSURE PROPER SEQUENCE OF OPERATIONS IN ACCORDANCE WITH APPROVED PLANS AND SPECIFICATIONS.
 4. ALL ECONOMIZERS SHALL BE ADJUSTED TO OPERATE IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
- C. PRELIMINARY COMMISSIONING REPORT - A PRELIMINARY REPORT OF COMMISSIONING TEST PROCEDURES AND RESULTS SHALL BE COMPLETED AND CERTIFIED BY THE REGISTERED DESIGN PROFESSIONAL (OR OTHERWISE APPROVED INDIVIDUAL) AND PROVIDED TO THE BUILDING OWNER. THE REPORT SHALL INCLUDE THE FOLLOWING:
 1. LIST OF DEFICIENCIES FOUND DURING THE TESTING REQUIRED BY THE COMMISSIONING PLAN THAT HAVE NOT YET BEEN CORRECTED AT THE TIME OF THE REPORT.
 2. LIST OF EQUIPMENT OR SYSTEMS NOT ABLE TO BE FUNCTIONALLY TESTED DUE TO UNFAVORABLE CURRENT CLIMATE CONDITIONS. THESE PIECES OF EQUIPMENT AND SYSTEMS WILL BE FUNCTIONALLY TESTED ONCE CLIMATE CHANGES ALLOW. TESTING IS DEFERRED UNTIL CLIMATE CONDITIONS ALLOW PROPER TESTING.
 3. DESCRIPTION OF NECESSARY CLIMATE CONDITIONS REQUIRED FOR FUNCTIONAL TESTING OF DEFERRED EQUIPMENT AND OR SYSTEMS.


* THE BUILDING, OR PORTION THEREOF, SHALL NOT PASS THE FINAL MECHANICAL INSPECTION UNTIL SUCH TIME AS THE CODE OFFICIAL HAS RECEIVED A LETTER OF TRANSMITTAL FROM THE BUILDING OWNER ACKNOWLEDGING THAT THE BUILDING OWNER HAS RECEIVED THE PRELIMINARY COMMISSIONING REPORT. THE CODE OFFICIAL MAY REQUIRE A COPY OF THE PRELIMINARY REPORT FOR REVIEW.

NOTE: THIS IS A LIST OF COMMONLY USED MECHANICAL AND PLUMBING SYMBOLS. SOME OF THE SYMBOLS SHOWN ABOVE MAY NOT BE USED IN THIS DRAWING PACKAGE.

MECHANICAL GENERAL NOTES

1. ALL MECHANICAL EQUIPMENT AND SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH THE INTERNATIONAL MECHANICAL CODE (IMC) LATEST EDITION, AND ALL APPLICABLE LOCAL AND STATE CODES.
2. ALL PLUMBING EQUIPMENT AND SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST ADOPTED PLUMBING CODE, AND ALL LOCAL AND STATE CODES.
3. ALL MECHANICAL AND PLUMBING EQUIPMENT SHALL BE INSTALLED PER THE MANUFACTURER'S RECOMMENDATIONS.
4. MECHANICAL CONTRACTORS SHALL RECEIVE PRIOR APPROVAL FROM THE STRUCTURAL ENGINEER BEFORE MAKING CUTS THROUGH ANY STRUCTURAL MEMBER.
5. MECHANICAL CONTRACTORS SHALL COORDINATE INSTALLATION WITH CONSTRUCTION SUPERVISOR AND WITH ALL OTHER TRADES TO AVOID CONFLICTS.
6. THE MECHANICAL CONTRACTORS SHALL VERIFY MOTOR VOLTAGES WITH THE ELECTRICAL DRAWINGS PRIOR TO ORDERING MOTORIZED EQUIPMENT AND CONTROLS.
7. SEE MECHANICAL SCHEDULE SHEET FOR SCHEDULED CAPACITIES OF ALL MECHANICAL EQUIPMENT AND MATERIALS SPECIFIED.
8. DOMESTIC WATER SERVICE IS PROVIDED WITH A DOUBLE-CHECK BACKFLOW PREVENTER ASSEMBLY.
9. THE PLUMBING CONTRACTOR IS RESPONSIBLE FOR ALL BACKFLOW DEVICES TO INSPECTED BY A CERTIFIED BACKFLOW TECHNICIAN BEFORE THE USE OF THE BUILDING POTABLE WATER SYSTEM.
10. ALL MECHANICAL EQUIPMENT TO BE PROPOSED MUST BE ON THE APPROVED LIST PRIOR TO SUBMITTALS. ALL APPROVED MANUFACTURERS MUST BE CAPABLE OF MEETING THE REQUIREMENTS OF THE SPECIFIED EQUIPMENT.
11. RUNOUT AND HOOKUP SIZES TO INDIVIDUAL PLUMBING FIXTURES CAN BE FOUND ON THE PLUMBING FIXTURE SCHEDULE.
12. PROVIDE REMOTE CEILING ACCESS BALANCE DAMPERS WITH CONCEALED CHROME PLATE COVERS FOR BALANCE DAMPERS LOCATED ABOVE HARD CEILINGS.
13. PAINT VTR'S, FLUES, EXHAUST CAPS, AND OTHER MECHANICAL ITEMS ON THE ROOF TO MATCH THE ROOF COLOR.
14. INSULATED FLEXIBLE DUCTWORK--IN LENGTHS OF 6'-0" OR LESS--MAY BE USED FOR RUNOUTS TO AIR TERMINALS.
15. MAINTAIN MINIMUM 10'-0" DISTANCE BETWEEN ALL FRESH AIR INTAKES AND EXHAUST OR GAS FLUE DISCHARGES.
16. LOCATE ACCESS HATCHES SO AS TO PROVIDE OPTIMUM SERVICEABILITY TO EQUIPMENT AND/OR VALVES. SEE ARCHITECTURAL SPECIFICATION FOR TYPE AND COLOR. COORDINATE LOCATION WITH ARCHITECTURAL, STRUCTURAL, AND LIGHTING.
17. WHENEVER THERE IS A DISCREPANCY BETWEEN THE RUNOUT DUCT SIZE SHOWN ON THE PLANS AND THAT SHOWN IN THE SCHEDULE, ALWAYS USE THE LARGER OF THE TWO DUCT SIZES.


[illegible]



SYMBOL USED FOR CALLOUT

2. SEE FURNACE INSTALLATION DETAIL.
3. SEE HOT WATER COIL INSTALLATION DETAIL.
4. INSTALL LOUVER 9'-0" A.F.F.
5. ROUTE 10" ROUND DUCT UP FROM BELOW AND CONNECT TO PENTHOUSE ON ROOF.
6. ROUTE CONCENTRIC VENTS FOR WH-2 & F-1 UP TO ROOF. SEE ROOF PLAN FOR CONTINUATION.
7. COORDINATE LOCATION OF DDC PANELS WITH DDC CONTRACTOR PRIOR TO INSTALLATION.
8. ROUTE 68"x22" SUPPLY DUCTWORK UP TO AIR HANDLER ON ROOF ABOVE. TRANSITION AND CONNECT TO AIR HANDLING UNIT.
9. INSTALL COMBINATION TEMPERATURE & HUMIDITY SENSOR ON WALL 42" A.F.F. COORDINATE WITH OTHER TRADES PRIOR TO FINAL INSTALLATION.
10. ROUTE SUPPLY DUCTWORK MAIN TIGHT TO STRUCTURE. COORDINATE DUCT ROUTING LOCATIONS WITH OTHER TRADES PRIOR TO FINAL INSTALLATION.
11. PROVIDE DUCT SMOKE DETECTOR ON RETURN DUCT.


TAG	EQUIPMENT NAME	MOUNTING	VENTILATION	OWNER SUPPLIED	CONSTRUCTION MANAGER SUPPLIED	INSTALLED BY	EXISTING	NEW	QTY
E001	AGGREGATE WASH	COUNTER				ITD	2		
E002	ASPHALT BATH WITH OWNER PROVIDED SHAFT ABOVE		IN SINK			ITD		3	4
E003	CONCRETE BATH	STAND		N	Y	Contractor		2	
E004	WAST								
E005	CONCRETE GRINDER	FLOOR				ITD	1	1	
E006	CONNECTION COVER	30" COUNTER		Y		FLOOR			
E007	GILSON COMPRESSOR MACHINE	FLOOR		Y	1	FLOOR			
E008	TUMBLER PORTAL SCREEN	30" COUNTER				SINK/WALL HOOD	ITD	1	1
E009	GILSON TESTING SCREEN	FLOOR				SINK/WALL HOOD	ITD	1	1
E010	GREEN BENCH OVER	30" COUNTER				CANOPY HOOD	ITD	6	
E011	HAMBURG WHEEL TRACKER	FLOOR				Y	ITD	1	1
E012	HEATED TAP	FLOOR				ITD	3	3	
E013	CLAM	COUNTER				ITD	1	1	
E014	INFRASTRATE EXTRACTOR	COUNTER				HOOD	ITD	1	1
E015	INSTRUCOR COLBOL	FLOOR				ITD	1	2	3
E016	RESTRICTOR CLOVER	20" COUNTER				ITD	1	1	
E017	LIFT BAR	OUTDOORS				ITD	1	1	
E018	MARY ANN LABORATORY SYSTEM	OUTDOORS				ITD	2	2	4
E019	NICK LA OVEN	FLOOR				ITD	4	2	6
E020	PINE SYRATORIO COMPRESSOR	30" COUNTER				ITD	2	1	3
E021	ROTOR	FLOOR				ROCK TO CONCRETE	ITD	1	1
E022	PROMOTOR BLOCK	FLOOR				ITD	2	2	
E023	RICE TAP (GILSON VIBRO DEBRATOR, PUMP JAWED, AIR FORCE CONTROLLER, SMALL COMPRESSOR) WITH OWNER PROVIDED SHEET PILED	30" COUNTER				ITD	2	1	3
E024	ROTARY EVAPORATOR	30" COUNTER				HOOD	ITD	1	1
E025	S.E. SYSTEM	30" COUNTER				ITD	2	2	
E026	SAF	FLOOR				ITD	1	1	
E027	SCALE	FLOOR				ITD	4	4	
E028	SHOCHILLER	30" COUNTER				ITD	1	1	
E029	ULTRASONIC CLEANER	COUNTER				ITD	1	1	1



EXHAUST PLAN
3/16" = 1'-0"

KEYED NOTES:

1. ROUTE EXHAUST DUCT UP AND TRANSITION TO LEF-1 PLENUM OPENING. COORDINATE WITH STRUCTURE TO ROUTE DUCT THROUGH JOISTS. SEE MECHANICAL ROOF PLAN FOR CONTINUATION.
2. EXTEND A FULL SIZE DUCT FROM THE ROOF-MOUNTED EXHAUST FAN THROUGH THE CEILING. TERMINATE THE DUCT WITH AN EXPANDED METAL SCREEN WITH A 1" FRAME. PAINT THE EXPANDED METAL AND ALL VISIBLE DUCTWORK THE SAME COLOR AS THE CEILING.
3. ROUTE 8" DUCT DOWN TO SNORKEL HOOD. PROVIDE WITH CEILING MOUNT BRACKET.
4. ROUTE 8" DUCT DOWN TO SNORKEL HOOD. PROVIDE WITH WALL MOUNT BRACKET.
5. ROUTE 3" STAINLESS STEEL FLEXIBLE FLUE DUCT FROM NCAT TO HOOD INLET. SUPPORT FLUE WITH BRACKET AND TERMINATE INDIRECTLY BELOW HOOD OPENING. PROVIDE WITH MANUAL DAMPER. (TYPICAL OF 2)
6. ROUTE 4" FLUE DUCT 2" ABOVE OVEN TO HOOD INLET. SUPPORT FLUE WITH BRACKET AND TERMINATE INDIRECTLY BELOW HOOD OPENING. (TYPICAL OF 2)
7. ROUTE EXHAUST DUCTWORK MAINS TIGHT TO STRUCTURE. COORDINATE DUCT ROUTING LOCATIONS WITH OTHER TRADES PRIOR TO FINAL INSTALLATION.
8. INSTALL CANOPY HOOD TIGHT TO WALL. PROVIDE WITH WALL BRACKETS AND ALL THREADS FOR SUPPORT FROM STRUCTURE. COORDINATE ADDITIONAL REQUIREMENTS WITH MANUFACTURER PRIOR TO FINAL INSTALLATION.



EXHAUST FLOOR PLAN


BID SET
5/13/2024

D-1 Testing Laboratory
600 W Prairie Ave
Coeur d'Alene, ID 83814

PROJECT NUMBER 23239
PRINCIPAL Designer
PROJECT MANAGER Author
M1.1

LAB EQUIPMENT LIST

TAG	EQUIPMENT NAME	MOUNTING	VENTILATION	OWNER	CONSTRUCTION	INSTALLED BY	EXISTING	NEW	QTY.
EQ1	AGGREGATE WASH	COUNTER		Y		ITD	2	2	2
EQ2	ASPHALT BATH WITH OWNER PROVIDED SHELF ABOVE	IN SINK				ITD	1	3	4
EQ3	CONCRETE BATH	STAND		N	Y	Contractor	2	2	2
EQ4	NOTIFIER					ITD	1	1	1
EQ5	CONCRETE GRINDER	FLOOR		Y		ITD	1	1	1
EQ6	CONNECTION OVEN	30" COUNTER		Y		ITD	4	4	4
EQ7	FORNEY COMPRESSION MACHINE	FLOOR		Y		ITD	1	1	1
EQ8	GILSON PORTA SCREEN	FLOOR	SNORKEL HOOD	Y		ITD	1	1	1
EQ9	GILSON TESTING SCREEN	FLOOR	SNORKEL HOOD	Y		ITD	1	1	1
EQ10	GREEN BENCH OVEN	30" COUNTER	CANOPY HOOD	Y		ITD	1	6	6
EQ11	HAMBERS WHEEL TRACKER	FLOOR		Y		ITD	3	3	3
EQ12	INSTRUTEC TABLE	COUNTER		Y		ITD	1	1	1
EQ13	IDEAL CT	COUNTER		Y		ITD	1	1	1
EQ14	INFRA-TEST EXTRACTOR	FLOOR	CANOPY HOOD	Y		ITD	1	1	1
EQ15	INSTRUTEC CORBELLO	20" COUNTER		Y		ITD	1	2	3
EQ16	INSTRUTEC CORBELLO	20" COUNTER		Y		ITD	1	2	3
EQ17	LAB BBQ	OUTDOORS		Y		ITD	1	1	1
EQ18	MARY ANNE LABORATORY SIFTER	FLOOR		Y		ITD	2	2	4
EQ19	NCAT LAB OVEN	30" COUNTER	CANOPY HOOD	Y		ITD	4	2	6
EQ20	PINE OPERATING COMPRESSOR	FLOOR		Y		ITD	2	1	3
EQ21	FLOOD COMPACTOR	1	BOLT TO CONCRETE	Y		ITD	1	1	1
EQ22	PROTECTOR BLOCK	FLOOR		Y		ITD	2	2	2
EQ23	RICE TABLE GILSON VIBRO-DEAERATOR, PUMP SAVER, AUTOFORCE CONTROLLER, SPHAL COMPRESSOR WITH OWNER PROVIDED SHELF / STAND	30" COUNTER		Y		ITD	2	1	3
EQ24	ROTARY EVAPORATOR	30" COUNTER	CANOPY HOOD	Y		ITD	2	1	1
EQ25	S.E. SYSTEM	30" COUNTER		Y		ITD	2	1	1
EQ26	SAW	FLOOR		Y		ITD	1	1	1
EQ27	SCALE	COUNTER		Y		ITD	4	4	4
EQ28	THERMO CHILLER	30" COUNTER		Y		ITD	1	1	1
EQ29	ULTRASONIC CLEANER	COUNTER		Y		ITD	1	1	1




 **HYDRONIC PLAN**
3/16" = 1'-0"

KEYED NOTES:

- ① SYMBOL USED FOR CALLOUT
- SEE HOT WATER COIL PIPING DETAIL FOR INSTALLATION REQUIREMENTS.
 - ROUTE 3" STEAM LINE UP TO AIR HANDLING UNIT ON ROOF. SEE ROOF PLAN FOR CONTINUATION.



MUSGROVE
ENGINEERING, P.A.
234 S. Whippewood Way
Boise, ID 83709
208.384.0585
645 West 25th Street
Idaho Falls, ID 83402
208.523.2862
www.musgrovepa.com
Project No. 23-239



PROJECT NUMBER 23239
PRINCIPAL Designer
PROJECT MANAGER Author



MICHAEL P. WALKER
STATE OF IDAHO

M1.2

LICENSED ARCHITECT
AAR-884931

D-1 Testing Laboratory
600 W Prairie Ave
Coeur d'Alene, ID 83814

HYDRONIC FLOOR PLAN
BID SET
5/13/2024

**MILLER
STAUFFER**
ARCHITECTS

601 E. FRONT AVE. STE 201
COEUR D'ALENE, IDAHO 83814
P 208.664.1773 F 208.667.3174
WWW.MILLERSTAUFFER.COM



HVAC Roof Plan

3/16" = 1'-0"




① SYMBOL USED FOR CALLOUT


1. ROUTE CONDENSIC VENT FROM FLOOR BELOW. SEAL ROOF PENETRATION.
2. ROUTE 8" ROUND FROM FLOOR BELOW AND TERMINATE WITH ROOF CAP.
3. INSTALL CONDENSING UNIT ON MIRO STAND PLATFORM PER DETAIL. ROUTE REFRIGERANT LINESET TO INDOOR FAN COIL UNIT. SEE DETAIL FOR REFRIGERANT PIPE ROUTING THROUGH ROOF.
4. ROUTE 3" STEAM LINE FROM FLOOR BELOW. USE HYDRONIC FLOOR PLAN FOR CONTINUATION. CONNECT TO AIR HANDLING UNIT AS REQUIRED.
5. ROUTE 3" FLUE AND INTAKE VENT FROM FLOOR BELOW. SEE FLOOR PLAN FOR CONTINUATION. PROVIDE GOOSENECK TURNDOWN ON INTAKE PER MANUFACTURER INSTALLATION REQUIREMENTS.
6. ROUTE CONDENSIC VENT FROM BOILER BELOW. PROVIDE WITH ROOF TERMINATION KIT. SEE FLOOR PLAN FOR CONTINUATION. PROVIDE GOOSENECK TURNDOWN ON INTAKE PER MANUFACTURER INSTALLATION REQUIREMENTS.
7. AIR HANDLING UNIT INSTALLED ON ROOF CURB. SEE ROOF CURB DETAIL FOR INSTALLATION REQUIREMENTS.
8. SEE PENTHOUSE MOUNTING DETAIL FOR INSTALLATION REQUIREMENTS.
9. SEE EXHAUST FAN FLAT ROOF MOUNTING DETAIL FOR INSTALLATION REQUIREMENTS.

NOTES:

- FOR TAKE-OFFS LARGER THAN 12" DIAMETER, USE A FACTORY MANUFACTURED DAMPER. LOUVERS & DAMPERS, INC. MODEL CD-600 WITH A LOCKING HAND QUADRANT OR EQUAL.
- ROD CONTINUOUS ON 2" W.G. CLASS AND ON ALL DAMPERS OVER 12" DIAMETER.
- BLADE 22 GAGE MIN., BUT NOT LESS THAN TWO GAGES MORE THAN THE DUCT GAGE.
- PROVIDE REMOTE CEILING OPERATOR WHERE DAMPER IS INACCESSIBLE.
- FOR DUCTS OVER 12" HIGH USE MULTIPLE BLADE DAMPERS (SEE FIG. C).
- ALTERNATE MANUFACTURERS INCLUDE: AMERICAN WARMING, SAFE-AIRDOWCO, J&J, LOUVERS & DAMPERS, RUSKIN, NAILOR, ARROW UNITED, POTTORFF, & CESCO.
- PROVIDE STAND-OFF FOR DAMPER ARMS LOCATED W/EXTERNAL INSULATION.




1 BALANCE DAMPER DETAIL
NTS




NOTES:

- SUPPORT SYSTEM SHALL NOT DAMAGE, CRIMP, OR INHIBIT DUCT FREE AREA IN ANY WAY.
- FLEXIBLE DUCT MUST NOT EXCEED 6'-0" FROM CONNECTION TO TERMINATION.
- MAXIMUM LENGTH BETWEEN SUPPORTS MUST NOT EXCEED 3'-0" ON CENTER.
- ATTACH BANDS OR WIRES TO SUPPORT STRUCTURE ABOVE.
- FLEXIBLE DUCTWORK SHALL BE FLEXMASTER 1-M OR APPROVED EQUAL.
- FLEXIBLE DUCTWORK SHALL BE INSULATED WITH A MINIMUM R-VALUE OF 6.0.
- FLEXIBLE DUCTWORK IS FOR INDOOR USE ONLY. DO NOT INSTALL OR STORE PRODUCT WHERE EXPOSURE TO DIRECT SUNLIGHT CAN OCCUR. PROLONGED EXPOSURE TO SUNLIGHT MAY CAUSE DETERIORATION OF VAPOR BARRIER.
- TERMINAL DEVICES SHALL BE SUPPORTED INDEPENDENTLY OF THE FLEXIBLE DUCTWORK.
- REPAIR TURN OR DAMAGED VAPOR BARRIER/JACKET WITH DUCT TAPE LISTED AND LABELED TO UL 181B. IF INTERNAL CORE IS PENETRATED, REPLACE FLEXIBLE DUCTWORK.
- AVOID BENDING DUCT ACROSS SHARP CORNERS OR INCIDENTAL CONTACT WITH METAL FIXTURES, PIPES, OR CONDUITS.
- FLEXIBLE DUCTWORK SHALL NOT BE INSTALLED WITHIN 4 INCHES OF HOT EQUIPMENT (FURNACES, BOILERS, STEAM PIPES, ETC.) THAT IS ABOVE 250°F.
- FLEXIBLE DUCTWORK SHALL NOT BE INSTALLED IN CONCRETE, BURIED BELOW GRADE, OR IN CONTACT WITH THE GROUND.
- DO NOT INSTALL FLEXIBLE DUCTWORK IN EXPOSED CEILING AREA.


4 FLEXIBLE DUCT SUPPORT DETAIL
NTS



2 DUCT TAKEOFF DETAIL - HIGH EFFICIENT
NTS




5 SPIRAL DUCT SUPPORT DETAIL (EXPOSED)
NTS



NOTE:

- ALL DUCTWORK TRANSITIONS SHALL BE CONSTRUCTED AND INSTALLED TO SMACNA, SPECIFICATIONS AND THE ABOVE NOTED STANDARDS. ANY DEVIATIONS SHALL BE COORDINATED WITH THE ENGINEER.


3 RECTANGULAR DUCT FITTING DETAILS
NTS



NOTE:

- ALL DUCTWORK TRANSITIONS SHALL BE CONSTRUCTED AND INSTALLED TO SMACNA, SPECIFICATIONS, AND THE ABOVE NOTED STANDARDS. ANY DEVIATIONS SHALL BE COORDINATED WITH THE ENGINEER.

6 ROUND DUCT FITTING DETAILS
NTS



MUSGROVE
ENGINEERING, P.A.
234 S. Whittemore Way
Boise, ID 83709
208.384.0585
645 West 25th Street
Idaho Falls, ID 83402
208.523.2862
www.musgrovepa.com
Project No. 23-239

MECHANICAL DETAILS


BID SET

5/13/2024


PROJECT NUMBER 23239
PRINCIPAL
PROJECT MANAGER
DESIGNER
AUTHOR
D-1 Testing Laboratory
600 W Prairie Ave
Coeur d'Alene, ID 83814
MICHAEL P. WALKER
STATE OF IDAHO
M4.0

MILLER
STAUFFER
ARCHITECTS


601 E. FRONT AVE. STE 201
COEUR D'ALENE, IDAHO 83814
P.208.664.1773 F.208.667.3174
WWW.MILLERSTAUFFER.COM




5 FURNACE INSTALLATION DETAIL (90%) NTS




6 DUCT TAKEOFF DETAIL - SPIRAL DUCT NTS




7 SEISMIC RESTRAINT FOR FLOOR MOUNTED EQUIPMENT DETAIL NTS




1 COMBUSTION AIR INTAKE DETAIL NTS



2 FLUE DETAIL NTS




3 DUCT LINER DETAIL NTS



4 CONCENTRIC VENT DETAIL NTS


5/14/2024 9:48:18 AM Autodesk Docs\\ITD D-1 Laboratory\\23239 ITD D1 Lab MEP_r23.rvt

- NOTES:
1. PIPING SHALL BE SUPPORTED INDEPENDENTLY FROM THE CONNECTIONS TO THE BOILER.
 2. INSTALL ALL VALVES IN ACCESSIBLE LOCATIONS FOR MAINTENANCE PURPOSES.
 3. INSTALL ALL GAUGES IN ACCESSIBLE LOCATIONS FOR MAINTENANCE / VIEWING PURPOSES.
 4. ALL BUTTERFLY VALVES MOUNTED HIGHER THAN ABOVE 7'-0" A.F.F SHALL BE PROVIDED W/ A CHAIN WHEEL AND GUIDES.




1 BOILER PIPING DETAIL
NTS

WESSELS MODEL NO.	PIPE SIZE "A"
NLAP 40, 60	3/4"
NLAP 100, 150	1"
NLAP 220	1-1/2"




- NOTES:
1. INSTALL ALL VALVES IN ACCESSIBLE LOCATIONS FOR MAINTENANCE PURPOSES.
 2. INSTALL ALL GAUGES IN ACCESSIBLE LOCATIONS FOR VIEWING PURPOSES.

5 VERTICAL EXPANSION PIPING DETAIL
NTS




- NOTES:
1. ALL COMPONENTS SHOWN SHALL BE EQUAL TO AUTOFLOW FLOW DESIGN, INC.
 2. INSTALL ALL AIR VENTS, STRAINERS, CONTROL VALVES, BALL VALVES, ETC. IN ACCESSIBLE LOCATIONS FOR MAINTENANCE PURPOSES.

2 HEATING COIL PIPING DETAIL
NTS




- NOTES:
1. THE WATER METER SHALL BE A DISPLACEMENT TYPE, FULL SIZE NUTATING DISC, MAGNETIC DRIVE, SEALED REGISTER AND FULLY CONFORM TO AWWA C700. PEAK DOMESTIC FLOW SHALL BE 30 GPM.
 2. THE WATER METER SHALL BE RATED FOR USE AT TEMPERATURES RANGING FROM -40 DEGREES F TO 158 DEGREES F AND OPERATE AT A WORKING PRESSURE OF 150 PSIG.
 3. THE METER CASE, BOTTOM CAPS, AND REGISTER BOX LIDS SHALL BE CONSTRUCTED FROM CAST BRONZE.

6 WATER METER PIPING DETAIL
NTS




- NOTES:
1. INSTALL ALL VALVES IN ACCESSIBLE LOCATIONS FOR MAINTENANCE PURPOSES.
 2. INSTALL ALL GAUGES IN ACCESSIBLE LOCATIONS FOR MAINTENANCE / VIEWING PURPOSES.
 3. ALL BUTTERFLY VALVES MOUNTED HIGHER THAN ABOVE 7'-0" A.F.F SHALL BE PROVIDED W/ A CHAIN WHEEL AND GUIDES.
 4. PROVIDE FLANGED, UNION, OR GROOVED FITTING AT THE PUMP.
 5. MOUNT THE PUMPS APPROXIMATELY 2'-6" AND 5'-0" ABOVE THE FINISHED FLOOR.

3 INLINE PUMP PIPING DETAIL
NTS




- NOTES:
1. INSTALL ALL VALVES IN ACCESSIBLE LOCATIONS FOR MAINTENANCE PURPOSES.
 2. INSTALL ALL GAUGES IN ACCESSIBLE LOCATIONS FOR MAINTENANCE / VIEWING PURPOSES.
 3. ALL BUTTERFLY VALVES MOUNTED HIGHER THAN ABOVE 7'-0" A.F.F SHALL BE PROVIDED W/ A CHAIN WHEEL AND GUIDES.

7 AIR SEPARATOR DETAIL
NTS



- NOTE:
1. INSTALL ALL VALVES IN ACCESSIBLE LOCATIONS FOR MAINTENANCE PURPOSES.
 2. INSTALL ALL GAUGES IN ACCESSIBLE LOCATIONS FOR VIEWING PURPOSES.

4 POT FEEDER PIPING DETAIL
NTS




8 FLOW METER PIPING DETAIL
NTS




MECHANICAL DETAILS

PROJECT NUMBER 23239
PRINCIPAL
PROJECT MANAGER
DESIGNER
AUTHOR
D-1 Testing Laboratory
600 W Prairie Ave
Coeur d'Alene, ID 83814
MICHAEL P. WALKER
STATE OF IDAHO
M4.2


MILLER
STAUFFER
ARCHITECTS
601 E. FRONT AVE. STE 201
COEUR D'ALENE, IDAHO 83814
P 208.664.1773 F 208.667.3174
WWW.MILLERSTAUFFER.COM




1 ROOFTOP CONDENSING UNIT PLATFORM DETAIL NTS




4 PIPING THROUGH ROOF DETAIL NTS




7 WALL MOUNTED SNORKEL INSTALLATION DETAIL NTS




8 CEILING MOUNTED SNORKEL INSTALLATION DETAIL NTS




2 ROOFTOP CONDENSING UNIT PLATFORM DETAIL NTS



5 EXHAUST FAN MOUNTING DETAIL NTS



3 PENTHOUSE MOUNTING DETAIL NTS



6 EXHAUST FAN MOUNTING DETAIL NTS

CONDENSING HOT WATER BOILER SCHEDULE											
SYMBOL	AREA SERVED	THERMAL EFFICIENCY	FUEL	EWT (°F)	LWT (°F)	BOILER FLOW (GPM)	MAX P.D. (FT H ₂ O)	CAPACITY		MANUFACTURER AND MODEL	REMARKS
								INPUT MBH	OUTPUT MBH		
B-1	HOT WATER LOOP	95%	NATURAL GAS	120.0	140.0	27.0	5.0	285	265	LOCHINVAR KHB285N	1, 2, 3, 4
B-2	HOT WATER LOOP	95%	NATURAL GAS	120.0	140.0	27.0	5.0	285	265	LOCHINVAR KHB285N	1, 2, 3, 4

- REMARKS:
- APPROVED ALTERNATE MANUFACTURERS: FULTON ENDURA, CLEAVER BROOKS CLEARFIRE, AERCO BENCHMARK.
 - PROVIDE BOILER VENTING KIT, BACnet INTERFACE, NEUTRALIZING KIT, COMBUSTION AIR INTAKE KIT, LOW WATER CUT-OFF, FLOW SWITCH, MODULATING GAS BURNER, CONDENSATE TRAP, 316L STAINLESS STEEL COMBUSTION CHAMBER, EXHAUST PIPE, CSD-1 AND OSA RESET, ~~ANALOG~~ CONTROL WITH 10:1 TURNDOWN.
 - BOILER SHALL BE PROVIDED W/FACTORY START-UP. START-UP IS NOT COMPLETE UNTIL ALL BURNERS AND BLOWER ARE CALIBRATED FOR PEAK PERFORMANCE AND AT COMPLETION OF PROJECT ALL BURNERS, BLOWERS, HEAT EXCHANGERS, AND OTHER INTERNAL PARTS SHALL BE THOROUGHLY CLEANED OF CONSTRUCTION DEBRIS.
 - SEE CONTROLS DRAWINGS FOR SEQUENCE OF OPERATION.
 - CAPACITY BASED ON 100% WATER.

HOT WATER REHEAT COIL SCHEDULE																	
SYMBOL	AREA / SUPPLY VALVE SERVED	CAPACITY (MBH)	CFM	E.A.T. (°F)	L.A.T. (°F)	AIR P.D. (IN W.C.)	FLUID PERFORMANCE			FLUID P.D. (FT)	ROWS	FPI	COIL SIZE		PIPING RUNOUT SIZE	MANUFACTURER AND MODEL	REMARKS
							E.W.T.	L.W.T.	GPM				WIDTH (IN)	HEIGHT (IN)			
HC-1	RESIDENCY LAB 131 / SAV-1	80.0	2,250	55.0	90.3	0.4	140.0	122.2	9.0	0.9	2	12	24	16	1-1/4"	DAIKIN 5WH1202B	1, 2, 3, 4, 5
HC-2	SOIL/AGGREGATE 126 / SAV-2	20.4	560	55.0	91.2	0.2	140.0	119.6	2.0	1.2	2	11	12	12	3/4"	DAIKIN 5BD1102B	1, 2, 3, 4, 5
HC-3	ASPHALT LAB 124 / SAV-3	80.2	2,260	55.0	90.2	0.4	140.0	122.2	9.0	0.9	2	12	22	16	1-1/4"	DAIKIN 5WH1202B	1, 2, 3, 4, 5
HC-4	D-1 LAB 123 / SAV-4	52.0	1,500	55.0	90.0	0.4	140.0	120.0	5.2	5.0	2	12	16	16	1"	DAIKIN 5BD1202B	1, 2, 3, 4, 5
HC-5	CONCRETE 119 / SAV-5	20.9	585	55.0	90.4	0.3	140.0	119.1	2.0	1.2	2	11	12	12	3/4"	DAIKIN 5BD1102B	1, 2, 3, 4, 5
HC-6	MATERIAL LAB 118 / SV-6	25.7	725	55.0	90.1	0.4	140.0	121.0	2.7	1.9	2	12	12	12	3/4"	DAIKIN 5BD1202B	1, 2, 3, 4, 5
HC-7	ASPHALT LAB 117 / SV-7	80.2	2,260	55.0	90.2	0.4	140.0	122.2	9.0	0.9	2	12	22	16	3/4"	DAIKIN 5WH1202B	1, 2, 3, 4, 5
HC-8	RESIDENCY NOISE ROOM 130 / SAV-8	22.3	630	55.0	90.1	0.3	140.0	120.6	2.3	10.3	2	10	12	12	3/4"	DAIKIN 5BD1002B	1, 2, 3, 4, 5
HC-9	GENERAL LAB 125 / SAV-9	45.6	1,290	55.0	90.1	0.4	140.0	119.3	4.4	6.6	2	12	16	14	1"	DAIKIN 5BD1202B	1, 2, 3, 4, 5

- REMARKS:
- APPROVED ALTERNATE MANUFACTURERS: CARRIER, TRANE, & USA COIL.
 - SEE DETAILS FOR REQUIRED VALVING.
 - CAPACITIES BASED ON 2,200 FEET ELEVATION.
 - CAPACITIES BASED ON 100% WATER.
 - PROVIDE BACnet INTEGRATION CARD. SEE CONTROL DRAWINGS FOR SEQUENCE OF OPERATION.

CONTROL VALVE SCHEDULE (HOT WATER REHEAT COILS)												
SYMBOL	HOT WATER COIL	AREA SERVED	VALVE TYPE	OPERATION	FLUID	FLOW (GPM)	FLOW RANGE (GPM)	P.D. (PSI)	MAXIMUM P.D. (PSI)	SIZE (IN)	MANUFACTURER AND MODEL	REMARKS
CV-1	HC-1	RESIDENCY LAB 131 / <u>SAV-1</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	9.0	6.0 TO 42.0	5.0	5.0	1-1/4"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5
CV-2	HC-2	SOIL/AGGREGATE 126 / <u>SAV-2</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	2.0	0.97 TO 5.85	5.0	5.0	3/4"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5
CV-3	HC-3	ASPHALT LAB 124 / <u>SAV-3</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	9.0	6.0 TO 42.0	5.0	5.0	1-1/4"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5
CV-4	HC-4	D-1 LAB 123 / <u>SAV-4</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	5.2	2.64 TO 15.89	5.0	5.0	1"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5
CV-5	HC-5	CONCRETE 119 / <u>SAV-5</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	2.0	0.44 TO 2.53	5.0	5.0	3/4"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5
CV-6	HC-6	MATERIAL LAB 118 / <u>SV-6</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	2.7	0.44 TO 2.53	5.0	5.0	3/4"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5
CV-7	HC-7	ASPHALT LAB 117 / <u>SV-7</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	9.0	0.44 TO 2.53	5.0	5.0	3/4"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5
CV-8	HC-8	RESIDENCY NOISE ROOM 130 / <u>SAV-8</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	2.3	0.44 TO 2.53	5.0	5.0	3/4"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5
CV-9	HC-9	GENERAL LAB 125 / <u>SAV-9</u>	PRESSURE INDEPENDENT FIELD ADJUSTABLE CONTROL VALVE W/ 100% AUTHORITY	2-WAY MODULATING	35% PROPYLENE GLYCOL	4.4	2.64 TO 15.89	5.0	5.0	1"	BELL & GOSSETT ULTRA SETTER	1, 2, 3, 4, 5

- REMARKS:
- APPROVED ALTERNATE MANUFACTURERS: BELIMO, SIEMENS, JOHNSON CONTROLS.
 - PROVIDE W/ MANUFACTURER'S PRESSURE INDEPENDENT FLOW ACCURACY WITHIN +/-5% OF DESIRED FLOW RATE UP TO 60 PSI, (2) PRESSURE / TEMPERATURE PORTS, EXTERNAL ADJUSTABLE DIAL W/ GPM SCALE, MODULATING FLOW CONTROL W/ LINEAR STROKE.
 - PROVIDE W/ MANUFACTURER'S 140 PSI CLOSE-OFF PRESSURE.
 - SEE CONTROL DRAWINGS FOR THE SEQUENCE OF OPERATION.
 - COORDINATE THE REQUIRED FLOW RATE W/ THE ACTUAL HOT WATER COILS PROVIDED.

HUMIDIFIER SCHEDULE															
SYMBOL	AREA SERVED	AREA R.H. / °F	STEAM CAPACITY	GAS INPUT	ELECTRIC REQUIREMENTS		OUTSIDE AIR		ENTERING DISTRIBUTOR		AIR STREAM SYSTEM		WATER SYSTEM	MANUFACTURER AND MODEL	REMARKS
			LBS OF STEAM/HR	MBH	AMPS	V/□	TEMP.	RH %	TEMP.	RH %	DUCT SIZE (WxH)	DUCT CFM			
<u>HUM-1</u>	AIR HANDLING UNIT <u>AHU-1</u>	30% / 70°	330	368.5	2.7	115/1	3°F	5%	55°F	6%	92"x70"	13,000	CITY / SOFTENED WATER	CAREL UG150H1105	1, 2, 3

- REMARKS:
- APPROVED ALTERNATE MANUFACTURERS: DRISTEAM AND NEPTRONIC.
 - PROVIDE WITH FULLY MODULATING CONTROL FUNCTIONS, RUBBER STEAM HOSES, STAINLESS STEEL STEAM DISTRIBUTOR, 3/8" CONDENSATE HOSE, STEAM INLET KIT, DUCT MOUNTED DIFFERENTIAL PRESSURE SENSOR, DUCT TEMPERATURE & RELATIVE HUMIDITY SENSOR, AND REMOTE PGDX TERMINAL KIT. PROVIDE FACTORY START-UP AND CALIBRATION.
 - CONNECT UNIT TO DDC CONTROL SYSTEM.

LAB EXHAUST FAN SCHEDULE														
SYMBOL	AREA SERVED	UNIT TYPE	BLOWER					ELECTRICAL		MAXIMUM SONES	OPERATING WEIGHT (LBS)	MANUFACTURER AND MODEL	REMARKS	
			CFM		ESP	MAXIMUM RPM	DRIVE	# OF FANS	HP PER FAN					V/O
			DESIGN	ACTUAL										
LEF-1	LAB AREA	NEW FUME EXHAUST FAN (HIGH-PLUME DILUTION)	15,000 (7,500 PER FAN)	12,310 (6,155 PER FAN)	4.0"	1,800	BELT	2	15.0	208/3	36	5,100	MK PLASTICS MODEL AXJUE1	1, 2, 3

- REMARKS:
- PROVIDE FAN WITH FRP AND POLYESTER-COATED-STEEL (4-6 MILS) CONSTRUCTION, 316SS HARDWARE, INTAKE WEATHER COWL, 42"Ø ROUND SIDE-INLET COLLAR, DRAIN AND ACCESS COVER, FLEX CONNECTOR, FAN ROOF CURB AND RAILS, SOUND ATTENUATOR, AND SPRING VIBRATION ISOLATION. UNIT SHALL HAVE AN EFFECTIVE PLUME HEIGHT OF 41.4' ABOVE FINISH ROOF ELEVATION.
 - CONTRACTOR SHALL PROVIDE AND INSTALL THE FOLLOWING OPTIONS AND SEQUENCE:
 - PROVIDE AND INSTALL THE FAN SYSTEM WITH THE FOLLOWING ITEMS TO ALLOW THE SYSTEM TO OPERATE AS A VARIABLE SPEED FAN SYSTEM:
 - (1) SHARED PLENUM WITH FACTORY BYPASS/ISOLATION DAMPERS (ANODIZED ALUMINUM, PARALLEL AIRFOIL CONSTRUCTION)
 - (2) NEW DISCONNECT SWITCHES WITH AUXILIARY CONTACTS
 - (2) VARIABLE FREQUENCY DRIVES (NEMA 3R)
 - THE SPEED OF THE FAN MOTORS AND BYPASS DAMPERS SHALL BE CONTROLLED THROUGH THE DDC CONTROLLER TO MAINTAIN A NOZZLE VELOCITY OF 5,000 FPM WHICH WILL PROVIDE AN EFFECTIVE PLUME HEIGHT OF 41.4 FEET AT MINIMUM FLOW REQUIREMENTS.
 - THE AIR BALANCING CONTRACTOR SHALL CONFIRM THAT THE NEW FAN STATIC CONTROLS ARE MAINTAINING THE STATIC PRESSURE SET POINT.

DIFFUSER SCHEDULE				
SYMBOL	NOMINAL SIZE	NECK / RUNOUT SIZE	CFM RANGE	REMARKS
D-1 CFM 60	6X6	6"Ø	0 - 90	1, 2, 3, 4, 5, 6, 7
D-2 CFM 100	10"Ø	10"Ø	0-350	1, 3, 4, 5, 6, 7, 9
D-3 CFM 120	12"Ø	12"Ø	0-400	1, 3, 4, 5, 6, 7, 9
D-4 CFM 140	14"Ø	14"Ø	0-550	1, 3, 4, 5, 6, 7, 9
D-5 CFM 60	13"Ø	6"Ø	0 - 90	1, 3, 4, 5, 6, 7, 8
D-6 CFM 80	18"Ø	8"Ø	90 - 200	1, 3, 4, 5, 6, 7, 8
D-7 CFM 100	22"Ø	10"Ø	200 - 350	1, 3, 4, 5, 6, 7, 8

- REMARKS:
- ALTERNATE MANUFACTURERS: ANEMOSTAT, J&J REGISTER, NAILOR, METAL-AIRE, TUTTLE & BAILEY, KRUEGER, PRICE, AND UNITED ENERTECH.
 - SIZES BASED ON TITUS MODEL TDC SERIES.
 - SIZES BASED ON A MAXIMUM NC LEVEL OF 25.
 - ALL DIFFUSERS LOCATED IN LAY-IN CEILING AREAS SHALL BE BORDER TYPE 3 AND BE MOUNTED IN MANUFACTURER PROVIDED 24"x24" PANELS. ALL DIFFUSERS LOCATED IN HARD CEILING AREAS SHALL BE BORDER TYPE 6 (BEVELED) SURFACE MOUNTED. SEE ARCHITECTURAL PLANS FOR LOCATIONS OF VARIOUS CEILING TYPES.
 - SEE HVAC FLOOR PLANS FOR DIRECTIONAL THROW REQUIREMENTS FOR EACH DIFFUSER.
 - WHENEVER THERE IS A DISCREPANCY BETWEEN THE RUNOUT DUCT SIZE SHOWN ON THE PLANS AND THAT SHOWN IN THE SCHEDULE, ALWAYS USE THE LARGER OF THE TWO DUCT SIZES.
 - COLOR TO BE SELECTED BY ARCHITECT.
 - SIZES BASED ON TITUS MODEL TMRA, TYPE 3, ROUND CEILING DIFFUSER, STEEL CONSTRUCTION.
 - SIZES BASED ON TITUS MODEL PAS, PERFORATED DIFFUSER, STEEL CONSTRUCTION.

BYPASS CONTROL VALVE SCHEDULE												
SYMBOL	SERVES	VALVE TYPE	OPERATION	FLUID	FLOW (GPM)	FLOW RANGE (GPM)	P.D. (PSI)	MAXIMUM P.D. (PSI)	SIZE (IN)	CONTROL	MANUFACTURER AND MODEL	REMARKS
BCV-1	HEATING WATER SYSTEM	PRESSURE INDEPENDENT	2-WAY MODULATING	100% WATER	25	19-110	2.7	5.0	2.0	REFER TO THE CONTROL SCHEMATICS	B&G ULTRA SETTER	1, 2, 3

- REMARKS:
- APPROVED ALTERNATE MANUFACTURERS: BELIMO, GRISWOLD, & ALFA-LAVAL.
 - CAPACITIES BASED ON 100% WATER.
 - SEE CONTROL DRAWINGS FOR SEQUENCE OF OPERATION.




MUSGROVE
ENGINEERING, P.A.
234 S. Whitewood Way
Boise, ID 83709
208.384.0585
645 West 25th Street
Idaho Falls, ID 83402
208.523.2862
www.musgrovepa.com
Project No. 23-239



AIR HANDLING UNIT SCHEDULE																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
SYMBOL	TYPE	AREA SERVED	SUPPLY FAN								DX / DEHUMIDIFICATION COOLING COIL								GAS HEATING COIL						HUMIDIFICATION COIL						COMBINATION FILTER						ELECTRICAL REQUIREMENTS			MIN. O.S.A. CFM	AHRI EER RATING	OPERATING WEIGHT (LBS)	MANUFACTURER AND MODEL	REMARKS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																					
			TYPE	AIRFLOW (CFM)		ESP	TSP	HP/QTY	V/PH	RPM	CAPACITY (MBH)		CFM	E.A.T. (°F)		L.A.T. (°F)		MAX FACE VELOCITY (FPM)	AIR P.D. (W.C.)	MAX RH	CAPACITY (MBH)		CFM	E.A.T. (°F)		L.A.T. (°F)		MODULATION %	UNIT TAG	COIL AIR P.D. (FT)	FINNED HEIGHT (IN)	FINNED WIDTH (IN)	FACE AREA (FT²)	FACE VEL. (FPM)	COIL TYPE	PRE-FILTER		FINAL FILTER							MAX FACE VELOCITY (FPM)	MCA	MIROPD	V/PH																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																	
				DESIGN	ACTUAL						SENSIBLE	TOTAL		D.B.	W.B.	D.B.	W.B.				INPUT	OUTPUT		D.B.	D.B.																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																								

- REMARKS:
- APPROVED ALTERNATE MANUFACTURERS: SCOTT SPRINGFIELD, TEMPTROL, HUNT AIR, & ENERGY LABS.
 - PROVIDE FAN ASSEMBLY WITH ECM MOTORIZED IMPELLER FANS.
 - EXTERNAL STATIC PRESSURE (ESP) DOES NOT INCLUDE THE COILS, FILTERS, OR OTHER INTERNAL AIR HANDLER LOSSES.
 - CAPACITIES FOR FANS AND COILS ARE BASED ON 2,200 FEET ELEVATION.
 - PROVIDE WITH 20" TALL VIBRATION ISOLATION ROOF CURB.
 - SEE HUMIDIFIER SCHEDULE FOR ADDITIONAL INFORMATION.



MECHANICAL SCHEDULES

BID SET
5/13/2024

LICENSED ARCHITECT
TAF-884931
MICHAEL P. WALKER
STATE OF IDAHO

D-1 Testing Laboratory
600 W Prairie Ave
Coeur d'Alene, ID 83814

PROJECT NUMBER 23239
PRINCIPAL
PROJECT MANAGER
DESIGNER
AUTHOR


M5.3

SYMBOL	DESCRIPTION
	ANALOG INPUT
	DIGITAL INPUT
	ANALOG OUTPUT
	DIGITAL OUTPUT
	CONTROL ELEMENT TAG
	3-WAY, 2-WAY CONTROL VALVE
	PARALLEL BLADE CONTROL DAMPER
	OPPOSED BLADE CONTROL DAMPER
	OPPOSED BLADE CONTROL DAMPER

- NOTES:**
- ALL DATA THAT IS NOTED TO BE "ADJUSTABLE" ON THE FOLLOWING CONTROL SHEETS SHALL MADE BOTH ADJUSTABLE AND LOCKABLE FROM THE OPERATOR'S WORKSTATION AND IN PARTICULAR, THE GRAPHICAL USER INTERFACE (GUI).
 - GLOBAL CALENDAR SCHEDULING SHALL BE PROVIDED.

SYMBOL	DESCRIPTION
	MOTOR
	THERMOWELL
	CURRENT SENSING RELAY
	CONTROL RELAY
	AIRFLOW MEASURING STATION (EBTRON GOLD SERIES) BY CONTROL CONTRACTOR
	DX REFRIGERANT COOLING COIL
	CHILLED WATER COOLING COIL
	HOT WATER HEATING COIL
	HEAT RECOVERY COIL
	HOT WATER PREHEAT COIL
	HOT WATER REHEAT COIL
	GAS-FIRED HEAT EXCHANGER
	THERMOSTAT
	SPACE TEMPERATURE SENSOR
	SPACE HUMIDITY SENSOR
	SPACE CARBON MONOXIDE SENSOR
	SPACE PRESSURE TRANSMITTER
	LOW VOLTAGE SIGNAL
	LINE VOLTAGE POWER

SYMBOL	DESCRIPTION
APS	AIRFLOW PROVING SWITCH
BAS	BUILDING AUTOMATION SYSTEM
BCV	BYPASS CONTROL VALVE
C	CONDENSATE
CFL	CONDENSATE FLOAT LEVEL SWITCH
CHWR	CHILLED WATER RETURN
CHWS	CHILLED WATER SUPPLY
CR	CONTROL RELAY
CSR	CURRENT SENSING RELAY
D	DAMPER
DA	DAMPER ACTUATOR
DDC	DIRECT DIGITAL CONTROLS
DPT	DAMPER POSITION TRANSMITTER
FS	FLOW SWITCH
GR	GLYCOL RETURN
GS	GLYCOL SUPPLY
HWR	HOT WATER RETURN
HWS	HOT WATER SUPPLY
LS	LIMIT SWITCH
PDS	PRESSURE DIFFERENTIAL SWITCH
PDT	PRESSURE DIFFERENTIAL TRANSMITTER
PS	PRESSURE SWITCH
PT	PRESSURE TRANSMITTER
TT	TEMPERATURE TRANSMITTER
TV	TEMPERATURE CONTROL VALVE
WL	WATER LEVEL SWITCH



CONTROL SYSTEM ARCHITECTURE

GENERAL:
THE DUCTLESS SPLIT SYSTEM SHALL CONSIST OF AN INDOOR FAN COIL UNIT, AN OUTDOOR HEAT PUMP UNIT, AND A MANUFACTURER PROVIDED WIRED CONTROLLER.

THIS SYSTEM SHALL BE STANDALONE. THE CONTROL CONTRACTOR SHALL MONITOR SPACE TEMPERATURE AND PROVIDE AN ALARM IF IT GETS TOO WARM.

OPERATION:
THE WIRED CONTROLLER SHALL CONTROL THE OPERATION OF THE DUCTLESS SPLIT SYSTEM.


COOLING MODE OF OPERATION:
IF COOLING IS REQUIRED, THE WIRED CONTROLLER SHALL ENABLE THE COMPRESSORIZED COOLING SYSTEM TO MAINTAIN THE USER ADJUSTABLE COOLING SPACE SET POINT. IF THE SPACE IS BELOW THE COOLING SET POINT, THE DUCTLESS SPLIT SYSTEM SHALL BE DISABLED.

THE SPACE TEMPERATURE COOLING SET POINT SHALL BE SET AT 75°F (ADJUSTABLE).

THIS SYSTEM SHALL BE LOCKED OUT OF THE HEATING MODE.

SAFETIES/ALARMS:
1. THE SYSTEM SHALL BE DISABLED WHENEVER THE WATER LEVEL OVERFLOW SWITCH INDICATES A HIGH CONDENSATE LEVEL.
2. IF THE SPACE TEMPERATURE INCREASES TO 80°F (ADJUSTABLE), AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.


DUCTLESS SPLIT SYSTEM SEQUENCE OF OPERATION (DFC-1/DCU-1)



DUCTLESS SPLIT SYSTEM CONTROL SCHEMATIC (DFC-1/DCU-1)

GENERAL:
ONE OUTSIDE AIR TEMPERATURE SENSOR SHALL BE INSTALLED ON THE NORTH SIDE OF THE BUILDING TO PROVIDE A CONTINUOUS READING OF THE OUTSIDE AIR TEMPERATURE.

OUTSIDE AIR TEMPERATURE SEQUENCE OF OPERATION



OUTSIDE AIR TEMPERATURE CONTROL SCHEMATIC

GENERAL:
THE HEAT RELIEF FAN W/ LOUVER UNIT SYSTEM CONSISTS OF A MOTORIZED INTAKE WALL LOUVER, MOTORIZED EXHAUST DAMPER, AN INLINE HEAT RELIEF FAN, AND A ZONE TEMPERATURE SENSOR. THE DDC CONTRACTOR SHALL PROVIDE A NEW DDC CONTROL PACKAGE DEDICATED TO THE COMPLETE OPERATION OF THE SYSTEM.

THE NEW SPACE TEMPERATURE SENSOR SHALL SIGNAL THE DDC CONTROLLER ITS TEMPERATURE AND THE TEMPERATURE OF THE COOLING SET POINT. THE SPACE TEMPERATURE SENSOR SHALL BE PROVIDED WITH A MANUAL OVERRIDE SWITCH TO START THE FAN AND OPEN THE DAMPERS.

HEAT RELIEF MODE OF OPERATION:
THE HEAT RELIEF FAN W/ LOUVER SYSTEM SHALL BE ENABLED WHENEVER THE FOLLOWING CONDITIONS BOTH EXIST:

- THE SPACE TEMPERATURE INCREASES ABOVE THE COOLING SET POINT.
- THE OUTDOOR AIR TEMPERATURE IS BELOW THE COOLING SET POINT.

WHEN THE ABOVE CONDITIONS EXIST THE DDC CONTROLLER SHALL SEQUENCE THE FOLLOWING:

- SEND AN OPEN COMMAND TO THE INTAKE WALL LOUVER.
 - VALIDATE THE POSITION OF THE INTAKE WALL LOUVER THROUGH THE DAMPER END SWITCH.
 - IF THE LOUVER FAILS TO OPEN, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.
- SEND AN OPEN COMMAND TO THE EXHAUST DAMPER.
 - VALIDATE THE POSITION OF THE EXHAUST DAMPER THROUGH THE DAMPER END SWITCH.
 - IF THE DAMPER FAILS TO OPEN, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.
- SEND AN ENABLE COMMAND TO THE HEAT RELIEF FAN TO RUN CONTINUOUSLY.
 - VALIDATE THE STATUS OF THE FAN THROUGH THE CURRENT SENSING RELAY.
 - IF THE FAN FAILS TO RUN, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.

THE HEAT RELIEF MODE OF OPERATION SHALL BE DISABLED WHENEVER THE FOLLOWING CONDITION EXISTS:


- THE SPACE TEMPERATURE REACHES 3°F BELOW THE COOLING SET POINT.

WHEN THE ABOVE CONDITION EXISTS THE DDC CONTROLLER SHALL SEQUENCE THE FOLLOWING:

- SEND A DISABLE COMMAND TO THE HEAT RELIEF FAN.
 - VALIDATE THE STATUS OF THE FAN THROUGH THE CURRENT SENSING RELAY.
 - IF THE FAN FAILS TO DISABLE, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.
- SEND A CLOSE COMMAND TO THE EXHAUST DAMPER.
 - VALIDATE THE POSITION OF THE EXHAUST DAMPER THROUGH THE DAMPER END SWITCH.
 - IF THE DAMPER FAILS TO CLOSE, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.
- SEND A CLOSE COMMAND TO THE INTAKE WALL LOUVER.
 - VALIDATE THE POSITION OF THE INTAKE WALL LOUVER THROUGH THE DAMPER END SWITCH.
 - IF THE LOUVER FAILS TO CLOSE, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.

THE SPACE TEMPERATURE COOLING SET POINT SHALL BE SET AT 85°F (ADJUSTABLE).
THE HEAT RELIEF FAN SHALL HAVE A MINIMUM OPERATION TIME OF 5 MINUTES (ADJUSTABLE)

HEAT RELIEF FAN W/ LOUVER SEQUENCE OF OPERATION (EF-6/L-1 & EF-7/L-2)



HEAT RELIEF FAN W/ LOUVER CONTROL SCHEMATIC (EF-6/L-1 & EF-7/L-2)

GENERAL:
THE HEAT RELIEF FAN UNIT SYSTEM CONSISTS OF MOTORIZED EXHAUST DAMPER, AN INLINE HEAT RELIEF FAN, AND A ZONE TEMPERATURE SENSOR. THE DDC CONTRACTOR SHALL PROVIDE A NEW DDC CONTROL PACKAGE DEDICATED TO THE COMPLETE OPERATION OF THE SYSTEM.

THE NEW SPACE TEMPERATURE SENSOR SHALL SIGNAL THE DDC CONTROLLER ITS TEMPERATURE AND THE TEMPERATURE OF THE COOLING SET POINT. THE SPACE TEMPERATURE SENSOR SHALL BE PROVIDED WITH A MANUAL OVERRIDE SWITCH TO START THE FAN AND OPEN THE DAMPERS.

HEAT RELIEF MODE OF OPERATION:
THE HEAT RELIEF SYSTEM SHALL BE ENABLED WHENEVER THE FOLLOWING CONDITIONS BOTH EXIST:

- THE SPACE TEMPERATURE INCREASES ABOVE THE COOLING SET POINT.
- THE OUTDOOR AIR TEMPERATURE IS BELOW THE COOLING SET POINT.

WHEN THE ABOVE CONDITIONS EXIST THE DDC CONTROLLER SHALL SEQUENCE THE FOLLOWING:

- SEND AN OPEN COMMAND TO THE EXHAUST DAMPER.
 - VALIDATE THE POSITION OF THE EXHAUST DAMPER THROUGH THE DAMPER END SWITCH.
 - IF THE DAMPER FAILS TO OPEN, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.
- SEND AN ENABLE COMMAND TO THE HEAT RELIEF FAN TO RUN CONTINUOUSLY.
 - VALIDATE THE STATUS OF THE FAN THROUGH THE CURRENT SENSING RELAY.
 - IF THE FAN FAILS TO RUN, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.

THE HEAT RELIEF MODE OF OPERATION SHALL BE DISABLED WHENEVER THE FOLLOWING CONDITION EXISTS:


- THE SPACE TEMPERATURE REACHES 3°F BELOW THE COOLING SET POINT.

WHEN THE ABOVE CONDITION EXISTS THE DDC CONTROLLER SHALL SEQUENCE THE FOLLOWING:

- SEND A DISABLE COMMAND TO THE HEAT RELIEF FAN.
 - VALIDATE THE STATUS OF THE FAN THROUGH THE CURRENT SENSING RELAY.
 - IF THE FAN FAILS TO DISABLE, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.
- SEND A CLOSE COMMAND TO THE EXHAUST DAMPER.
 - VALIDATE THE POSITION OF THE EXHAUST DAMPER THROUGH THE DAMPER END SWITCH.
 - IF THE DAMPER FAILS TO CLOSE, AN ALARM OF THE EVENT SHALL BE SENT TO THE OPERATOR'S WORKSTATION.

THE SPACE TEMPERATURE COOLING SET POINT SHALL BE SET AT 85°F (ADJUSTABLE).
THE HEAT RELIEF FAN SHALL HAVE A MINIMUM OPERATION TIME OF 5 MINUTES (ADJUSTABLE)

HEAT RELIEF FAN SEQUENCE OF OPERATION (EF-5)




HEAT RELIEF FAN CONTROL SCHEMATIC (EF-5)



HEATING WATER SYSTEM CONTROL SCHEMATIC

[illegible]



① SYMBOL USED FOR CALLOUT


1. STORM LINE LEAVING BUILDING AT 30" BFF. SEE CIVIL SITE PLAN FOR CONTINUATION.
2. THE WASTE LINE INVERT ELEVATION AT THIS LOCATION IS 54" BELOW FINISHED FLOOR (BFF). THE INVERT ELEVATION IS BASED ON A STARTING POINT OF 24 INCHES BFF WITH A LINE SLOPE OF 1/4" PER FOOT. SEE CIVIL SITE PLAN FOR CONTINUATION.
3. ROUTE 3' RD FROM ABOVE. SEE PLUMBING FLOOR PLAN FOR CONTINUATION.
4. GAS LINE FROM INTERMOUNTAIN GAS COMPANY. SEE CIVIL DRAWINGS FOR CONTINUATION.
5. 2" DOMESTIC WATER LINE ROUTED FROM NEW 1-1/2-INCH WATER METER. SEE CIVIL PLANS FOR CONTINUATION.
6. ROUTE 4' RD FROM ABOVE. SEE PLUMBING FLOOR PLAN FOR CONTINUATION.
7. ROUTE VENT FROM TRENCH DRAIN UNDERGROUND.
8. ROUTE 1-1/4" WASTE FROM ES-1 AND COMBINE WITH 4" WASTE FROM FD-2.



⑧ SYMBOL USED FOR CALLOUT

1. ROUTE 2" WATER LINE UP FROM FLOOR BELOW. SEE FOUNDATION PLUMBING PLAN FOR CONTINUATION.
2. ROUTE 1/2" CA LINE DOWN WALL AND CONNECT TO LAB EQUIPMENT. COORDINATE LAB EQUIPMENT LOCATION PRIOR TO FINAL INSTALLATION.
3. ROUTE 2" DRAIN FROM AHU ON ROOF. TERMINATE INDIRECTLY AT FLOOR SINK.
4. GAS METER FURNISHED AND INSTALLED BY LOCAL GAS COMPANY. REFER TO GAS SIZING CHART FOR ADDITIONAL INFORMATION.
5. ROUTE GAS LINE UP THROUGH ROOF TO UNIT ON ROOF. SEE ROOF PLAN FOR CONTINUATION.
6. ROUTE 1/2" HW FROM US-1 TO RBPB AND CONNECT TO EQ-29. TERMINATE RBPB DRAIN AT FLOOR SINK UNDER US-1.
7. ROUTE 3/4" CW & HW DOWN TO RBPB'S. CONNECT TO LAB EQUIPMENT AS REQUIRED.
8. ROUTE EXPOSED CW & HW PIPING DOWN WALL TO PLUMBING FIXTURE. SUPPORT PIPE ON WALL WITH BRACKETS.
9. ROUTE CW & HW PIPING DOWN WALL TO EMERGENCY SHOWER TEMPERING STATION. COORDINATE TEMPERING STATION WITH OTHER TRADES ON WALL PRIOR TO INSTALLATION.
10. ELECTRONIC TRAP PRIMER LOCATED ON WALL. ROUTE 3/4" CW TO TRAP PRIMER AND UNDERGROUND TRAP PRIMER PIPING TO FIXTURES PER DETAIL.
11. ROUTE 3" RD & OD FROM ROOF ABOVE. SEE PLUMBING ROOF PLAN FOR CONTINUATION.
12. ROUTE 4" RD & OD DOWN WALL IN ELECTRICAL ROOM. COORDINATE ROUTING WITH ELECTRICAL PANELS TO MAINTAIN ELECTRICAL CLEARANCE REQUIREMENTS.
13. ELECTRONIC TRAP PRIMER LOCATED ON WALL. ROUTE 3/4" CW FROM UTILITY SINK TO TRAP PRIMER AND UNDERGROUND TRAP PRIMER PIPING TO FIXTURES PER DETAIL.
14. ROUTE CONDENSATE DRAIN TO NEAREST FLOOR SINK AND TERMINATE INDIRECTLY.
15. ROUTE 1" CW UP TO ROOF HYDRANT ON ROOF ABOVE. SEE ROOF PLAN FOR CONTINUATION. PROVIDE WITH MANUAL SHUTOFF VALVE BELOW CEILING.
16. ROUTE DRAIN FROM ROOF HYDRANT TO FLOOR SINK IN OFFICE MECHANICAL 113.
17. ROUTE EXPOSED CW DOWN WALL. COORDINATE WITH ALL OTHER TRADES PRIOR TO FINAL INSTALLATION.
18. ROUTE EXPOSED NPWC DOWN AND CONNECT TO LAB EQUIPMENT AS REQUIRED.
19. ROUTE EXPOSED 1-1/2" TEMPERED WATER TO EMERGENCY SHOWER.

QTY	TAG	EQUIPMENT NAME	HOISTING	COLD WATER	HOT WATER	WASTE	AIR	OWNER SUPPLIED	CONSTRUCTION MANAGER SUPPLIED	INSTALLED BY	EXISTING	NEW	QTY
1	E001	ACROBAT, 18" HIGH	COUNTER							Y			1
2	E002	ASPHALT BATH WITH OWNER PROVIDED SHIP ABOVE	IN BINK STAND							ITD	2	3	4
3	E003	CONCRETE BATH						N	Y	Contractor		2	2
4	E004	REFUSE											
5	E005	CONCRETE GRENDER	FLOOR	1/2"				INDIRECT	Y	ITD	1	1	1
6	E006	CONNECTION OVER	3P COUNTER							ITD	4	4	4
7	E007	FORMAL COMPRESSOR MACHINE	FLOOR							ITD	1	1	1
8	E008	GILSON PORTA SCREEN	FLOOR							ITD	1	1	1
9	E009	GILSON TESTING SCREEN	FLOOR							ITD	1	1	1
10	E010	GRIND BRUSH OVER	3P COUNTER							ITD	1	1	8
11	E011	HANDING WHEEL TRIGGER	FLOOR	1/2"	1/2"			INDIRECT	1/2"	Y	ITD	1	1
12	E012	RELATED FLOOR								ITD	1	1	3
13	E013	IDEAL KIT	COUNTER							ITD	1	1	1
14	E014	IMPULSION EXTRACTOR	FLOOR					1/2"		ITD	1	1	1
15	E015	INSTRUTOR CORRELX	2P COUNTER							ITD	1	2	3
16	E016	INSTRUTOR CORRELX	2P COUNTER							ITD	1	1	1
17	E017	LAB BNC	OUTDOORS							ITD	1	1	1
18	E018	MANUAL LABORATORY TESTER	FLOOR							ITD	1	1	4
19	E019	MEAT LAB	3P COUNTER							ITD	4	2	6
20	E020	PHIL CRAMON LAB OVER	FLOOR							ITD	1	1	1
21	E021	PROOF COMPACTOR	BOLT TO CONCRETE							ITD	1	1	1
22	E022	PULLION BLOCK	FLOOR							ITD	2	2	2
23	E023	REF. TABLE (ON CASE VERO) REARATOR, PUMP, SAVER, AUTOFORCE CONTROLLER, CHAL. COMPRESSOR, WITH OWNER PROVIDED SHELF/STAND								ITD	1	1	3
24	E024	ROTARY EXHAUSTOR	3P COUNTER					Y	ITD		1	1	1
25	E025	S.E. SYSTEM	3P COUNTER							ITD	2	2	2
26	E026	SFW	FLOOR							ITD	1	1	1
27	E027	SCALE	FLOOR							ITD	1	1	4
28	E028	SHEDDING CHILLER	3P COUNTER							ITD	1	1	1
29	E029	ULTRASONIC CLEANER	COUNTER		Y					ITD	1	1	1



601 E. FRONT AVE. STE 201
COEUR D'ALENE, IDAHO 83814
P 208.664.1773 F 208.667.3174
WWW.MIIIFIRSTAIDIFFER.COM

PLUMBING ROOF PLAN

BID SET
5/13/2024

LICENSED
ARCHITECT

D-1 Testing Laboratory

600 W Prairie Ave
Coeur d'Alene, ID 83814

LICENSED
ARCHITECT
AR-984931

HEAL P. WALKER
STATE OF IDAHO

P3.0	PROJECT NUMBER	23239	
	PRINCIPAL	TN	
	PROJECT MANAGER	CD	
	No.	Description	Date

P3.0

⑧ SYMBOL USED FOR CALLOUT

1. ROUTE 1-1/4" MPG LINE UP THROUGH ROOF AND CONNECT TO AHU. SEE GAS PIPING CONNECTION DETAILS FOR INSTALLATION REQUIREMENTS. SEE PLUMBING FLOOR PLAN FOR CONTINUATION.
2. ROUTE 2" DRAIN DOWN THROUGH ROOF TO FLOOR BELOW. SEE PLUMBING FLOOR PLAN FOR CONTINUATION.



 FIRE SPRINKLER FLOOR PLAN
3/16" = 1'-0"


KEYED NOTES:

SYMBOL USED FOR CALLOUT

1. FIRE SPRINKLER LINE TO BE SIZED AND INSTALLED BY FIRE SPRINKLER CONTRACTOR. REFER TO SPECIFICATIONS FOR ADDITIONAL FIRE SPRINKLER SYSTEM REQUIREMENTS. SEE CIVIL DRAWINGS FOR CONTINUATION.
2. ROUTE FIRE SPRINKLER LINE UP FROM BELOW FLOOR. SEE FOUNDATION PLUMBING PLAN FOR CONTINUATION.
3. AREA RESERVED FOR FIRE SPRINKLER RISER SYSTEM. FIRE SPRINKLER RISER SYSTEM SHALL INCLUDE A TAMPER SWITCH, FLOW SWITCH, ALARM BELL, FIRE DEPARTMENT CONNECTION, AND POST INDICATOR VALVE (PIV).

FIRE SPRINKLER NOTES:

- A. THE FIRE SPRINKLER SYSTEM SHALL BE DESIGNED AND INSTALLED BY THE FIRE SPRINKLER CONTRACTOR. THIS PLAN INDICATES GENERAL PARAMETERS THE FIRE SPRINKLER CONTRACTOR MUST DESIGN AND INSTALL AROUND. THE ENGINEER/ARCHITECT/OWNER RESERVES THE RIGHT TO REVIEW AND APPROVE TEST VALVES, ZONING VALVES, FLOW SENSORS, ETC. DURING THE SUBMITTAL PROCESS.
- B. FIRE SPRINKLER CONTRACTORS SHALL BE LICENSED BY THE IDAHO STATE FIRE MARSHAL, AND SHALL HAVE IN HIS/HER EMPLOY AND WITHIN 50 MILES OF THE JOB SITE AN ENGINEERING TECHNICIAN (LEVEL III), CERTIFIED BY NICET (NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES). PROOF OF BOTH MUST BE SUBMITTED TO THE ENGINEER PRIOR TO THE START OF ANY FIRE SPRINKLING DESIGN AND/OR INSTALLATION. NO EXCEPTIONS.
- C. ALL WORK REQUIRED FOR THE FIRE PROTECTION SYSTEM SHALL BE THE RESPONSIBILITY OF THE FIRE SPRINKLER CONTRACTOR. THE FIRE SPRINKLER SYSTEM SHALL BE INSTALLED BY THE FIRE SPRINKLER CONTRACTOR AS REQUIRED TO SATISFY THE REQUIREMENTS OF THE LOCAL JURISDICTION AND NFPA 13, LATEST EDITION. ARCHITECT/ENGINEER ASSUMES NO RESPONSIBILITY OR LIABILITY FOR THE DESIGN OF THE FIRE SPRINKLER SYSTEM.
- D. REFER TO FIRE SPRINKLER SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- E. PROVIDE RECESSED HEADS IN ALL AREAS EXCEPT WHERE ROOM IS OPEN TO STRUCTURE.
- F. NO STANDOFF SPRINKLER HEADS (THOSE THAT DROP BELOW CEILING OR SOFFIT TO PROVIDE BETTER COVERAGE) ALLOWED. ALL SPRINKLER HEADS MUST BE FLUSH WITH CEILING OR EXTERIOR SOFFIT.
- G. REFERENCE ARCHITECTURAL SECTIONS FOR LOCATION OF BUILDING INSULATION ENVELOPES.
- H. PIPE ALL AUXILIARY DRAINS TO EXTERIOR OF BUILDING OR APPROVED RECEPTACLE. COORDINATE WITH ARCHITECT.
- I. IN COLD SPACES WHERE A NON-FREEZE FIRE SPRINKLER SYSTEM IS REQUIRED, CONTRACTOR SHALL PROVIDE A DRY PIPE SPRINKLER SYSTEM.



FIRE SPRINKLER FLOOR PLAN

LICENSED ARCHITECT
AAR-884931
D-1 Testing Laboratory
600 W Prairie Ave
Coeur d'Alene, ID 83814
MICHAEL P. WALKER
STATE OF IDAHO

PROJECT NUMBER 23239
PRINCIPAL TN
PROJECT MANAGER CD

FS1.0

BID SET
5/13/2024

601 E. FRONT AVE. STE 201
COEUR D'ALENE, IDAHO 83814
P.208.664.1773 F.208.667.3174
WWW.MILLERSTAUFFER.COM

MILLER
STAUFFER
ARCHITECTS